

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED IN MACOMB COUNTY

RECORDS AT: 8:30 A.M.

For corners in

Macomb (County)

Located In: Washington Twp. Corner Code # G-13

DEC 28 1993

Carroll A. ... CLERK - REGISTER OF DEEDS MACOMB COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 4 R 12 G-13
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. A dot is present in row 13, column G.

I, Huston K. Kennedy, in a field survey on December 10, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set post; 30" Lynn S46°W 20 Lnks; 20" Lynn N31°E 29 Lnks
1976-Kobs, P.S. #14097; Survey L.2723, Pg.872 - Fnd Chiseled cross in concrete pavement.
1977-Kobs, P.S. #14097; Survey L.2811, Pg.745 - Same wits as 1976 Survey
1979-Kobs, P.S. #14097; Survey L.3074, Pg.521 - Same wits as 1976 Survey
1989-Avey, P.S. #30076; LCRC L.4584, Pg.238 - Fnd chiseled cross in concrete pavement
1993-King, P.S. #30085; Survey L.5831, Pg.305 - Same wits as 1979 Survey

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd chiseled cross that is located 1' West of the centerline of Van Dyke Road and in the center of the Boulevard of 26 Mile Road. Both are concrete surface roads.

Two witness points from the 1989 LCRC were found and they were used to recover and verify the found chiseled cross.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-15-93. FRANK J. DeDECKER, PS, PE, CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

- G-13 I replaced the found chiseled cross with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" in a monument box.
S79°E-36.35'-Set PK Nail & Remon. tag in South face Power Pole
N27°E-87.87'-Set PK Nail & Remon. tag above existing witness in SE face Power Pole
S86°W-35.31'-Set PK Nail & Remon. tag in North face Power Pole
S34°W-92.63'-Set PK Nail & Remon. tag in NW face Power Pole

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature] Surveyor's Michigan License No. 17623

Date 12-10-93

