

**SURVEY &
REMONUMENTATION**

C126149

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE

94 SEP 30 AM 9:00

For corners of **COMMISSION**

Filing Requirement of Act 74, Mich. P.A. 1970

**CARMEL J. SAUGH
REGISTER OF DEEDS
MACOMB COUNTY, MI**

Macomb
(County)

Located In: Washington Township Corner Code #

- | | | | | | |
|------------------------------------|---|-----------|---|------------|------------|
| 1. Public Land Survey | T | <u>4N</u> | R | <u>12E</u> | <u>H-7</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

FILED 06464PG462

Register of Deeds Stamp & File Number

I, Huston K. Kennedy, in a field survey on August 21, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set Post; 12" Lynn S57°W 20 Links; 12" Lynn N45°W 21 Links
- 1976-Smith, P.S. #16052; LCRC L.2747, Pg.597 - Fnd 3/4" Rod in a Monument Box
 - 1990-Nelson, P.S. #21273; LCRC L.4816, Pg.948 - Fnd 1/2" Pipe in a Monument Box
 - 1976-Smith, P.S. #16052; Survey L.2747, Pg.596 - Fnd 3/4" Iron Rod in a Monument Box
 - 1979-Kobs, P.S. #14097; Survey L.3074, Pg.519 - Fnd 1/2" Pipe in a Monument Box
 - 1992-King, P.S. #30085; Survey L.5778, Pg.395 - Fnd 1/2" Iron Pipe in a Monument Box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. Kennedy, P.S. #17623 - Fnd 3/4" Iron Rod in a Monument Box in the centerline of 29 Mile Road, which has a bituminous surface, with a tree row extending to the North.

Witnesses from LCRC #1 & 3 were used to recover and verify the location of the found 3/4" Iron Rod in a Monument Box.

FIELD MEASUREMENT BETWEEN

- H-7 to G-7 2638.86 Feet
- H-7 to I-7 2541.45 Feet

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 8-30-94

William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- H-7 I replaced the 3/4" Iron Rod in a Monument Box with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" in a existing Monument Box.
- N72°E 156.70' Set PK & Remon. Washer South face Power Pole
 - N73°W 125.56' Set PK & Remon. Washer South face Power Pole
 - N06°W 34.97' Set PK & Remon. Washer East face 11" Walnut
 - N63°E 130.81' Set PK & Remon. Washer NW face 27" Elm

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by *Huston K. Kennedy* Date August
Surveyor's Michigan License No. 17623

