

**SURVEY &
REMONUMENTATION**

APR 28 1995

C105006

LAND CORNER RECORDATION CERTIFICATE

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Washington

Macomb
(County)

Located In: Township _____ Corner Code # _____

118FR **06415PC483**

1. Public Land Survey	T	<u>4</u>	N	R	<u>12</u>	E	<u>H-9</u>
	T	_____	R	_____	_____	_____	_____
	T	_____	R	_____	_____	_____	_____
	T	_____	R	_____	_____	_____	_____
2. Property Controlling in Section	S	_____	T	_____	R	_____	_____
	S	_____	T	_____	R	_____	_____
3. Miscellaneous Property in Sec.	S	_____	T	_____	R	_____	_____
	S	_____	T	_____	R	_____	_____

94 AUG -5 PM 1:43

CARMEL R. SAGAUGH
REGISTER OF DEEDS
MACOMB COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Huston K. Kennedy, in a field survey on June 15, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, Set Post; 5" Elm S56+E 15 Links; 20" Lynn N88+W 21 Links
 1.) 1973-Kobs, P.S. #14097; LCRC L.2360, Pg.804 - Fnd 1/2" Iron Bar in a Monument Box
 2.) 1988-Avey, P.S. #30076; LCRC L.4353, Pg.429 - Fnd 1/2" Iron Bar in a Monument Box
 3.) 1989-Donnelly, P.S. #21563; LCRC L.4723, Pg.604 - Found 1/2" Iron Rod in a Monument Box
 4.) 1973-Kobs, P.S. #14097; Survey L.2360, Pg.829 - Same wit as 1973 LCRC

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. Kennedy, P.S. #17623 - Fnd 1/2" Iron Rod in a Monument Box 4.5' North of the centerline of 28 Mile Road, which has a bituminous surface, and a fence row extending to the South, and TRW Shop to the North.

Witnesses from LCRC #1, 2 & 3 were used to recover and verify the location of the found 1/2" Iron Rod in a Monument Box.

FIELD MEASUREMENT BETWEEN

H-9 to G-9 2549.86 Feet
H-9 to I-9 2620.50 Feet

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER
GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN
PUBLIC ACT 345 OF 1990 AT A MEETING HELD
ON 7-19-94
William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-9 I replaced the found 1/2" Iron Rod in a Monument Box with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" in a existing Monument Box.
 S45'W 58.25' Set PK & Remon. Washer SE face Power Pole
 S75'E 117.93' Set PK & Remon. Washer NE face Power Pole
 N10'W 29.84' Set PK & Remon. Washer East face 21" Elm
 N30'E 38.88' Set PK & Remon. Washer NW face 15" Elm

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.



Signed by *Huston K. Kennedy*
Surveyor's Michigan License No. 0623

Date July 21, 1994