

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Macomb

(County)

Washington Twp

Located in:

Corner Code #

- |                                    |              |               |            |
|------------------------------------|--------------|---------------|------------|
| 1. Public Land Survey              | T <u>4</u> N | R <u>12</u> E | <u>I-1</u> |
|                                    | T _____      | R _____       | _____      |
|                                    | T _____      | R _____       | _____      |
|                                    | T _____      | R _____       | _____      |
| 2. Property Controlling in Section | S _____      | T _____       | R _____    |
|                                    | S _____      | T _____       | R _____    |
| 3. Miscellaneous Property in Sec.  | S _____      | T _____       | R _____    |
|                                    | S _____      | T _____       | R _____    |

**SURVEY & REMONUMENTATION**

FEB 27 1997

COMMISSION

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Huston K. Kennedy, in a field survey on April 22, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

|    | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |   |

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set Post 26" White Oak N75°W 1.53 Chains; 22" White Oak S08°E 1.24 Chains  
 1.) 1979-Verba, PS #13603; LCRC L.3074, Pg.6 - Fnd 4" Plug  
 2.) 1981-Kobs, PS #14097; LCRC L.3385, Pg.268 - Fnd 1" Iron Bar in pavement

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 5-21-96

William E. Soderberg  
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1996 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd Railroad Spike 3" below the surface in the existing center of 32 Mile Road, which has a bituminous surface extending to the East & West, also 20.5 feet East of the existing centerline of Sisson Street, which has a bituminous surface extending to the South and 29 feet East of the existing centerline of Chandler Street extending to the North, which has a bituminous surface. A corner common to Sections 34 & 35, T5N, R12E, Bruce Twp., (I-13) is located 7.22 feet to the West. The corner I-1 was set on a straight line between I-13 and J-13.

Witnesses from LCRC #1 & 2 were used to recover and verify the location of the found Railroad Spike.

FIELD MEASUREMENTS BETWEEN

- I-1 to I-2 GLO = 47.97 chains or 3166.02 Ft. & 3184.99 Ft. (GPS-MEA)  
 I-1 to I-13 GLO = 11 links or 7.26 Ft. & 7.22 Ft. (MEA)  
 I-1 to J-1 2669.08 Ft. (GPS-MEA), No GLO

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-1 I set a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345" #17623 in a new Monument Box  
 N12°W 35.68' Set PK & Remon Washer East face Power Pole  
 N61°E 52.65' Set PK & Remon Washer SE face 18" Maple  
 S54°E 54.58' Set PK & Remon Washer NE face 25" Maple  
 S63°W 52.95' Set PK & Remon Washer NW face Power Pole  
 North 0.58 feet Railroad Spike  
 West 7.22 feet corner common to Sections 34 & 35, T5N, R12E, Bruce Twp., (I-13)

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.



Signed by [Signature]  
 Surveyor's Michigan License No. 17623

Date 12-6-96

630