

SURVEY & REMONUMENTATION

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE

0152198

Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

corners in

Macomb
(County)

Located In: Washington Corner Code #
Twp.

LIBER 6527 PAGE 775

Public Land Survey	T	<u>4N</u>	R	<u>12E</u>	<u>I-5</u>
	T		R		
	T		R		
	T		R		
Property Controlling in Section	S		T		
Miscellaneous	S		T		
Property in Sec.	S		T		

94 DEC 14 AM 10:50

RECORDED
MACOMB COUNTY, MI

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Huston K. Kennedy, in a field survey on September 10, 1994

hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the present manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as pressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

- 17-GLO Wampler, D.S.; Set Post; ? S65°E 33 Links; 22" Red Oak N42°W 53 Links
-) 1975-Kobs, P.S. #14097; LCRC L.2590, Pg.224 - Fnd 3/8" Iron Rod
-) 1975-Hooth, P.S. #7966; LCRC L.2621, Pgs.699-700 - Set section corner from witnesses of previous survey and adjacent properties. Set 3/4" Iron Rod in a Monument Box.
-) 1984-Kobs, P.S. #14097; LCRC L.3705, Pg.145 - Fnd 3/4" Iron Bar in a Monument Box
-) 1979-Dunn, P.S. #5577; Survey L.3084, Pg.709 - Fnd 3/4" Iron Bar in a Monument Box
-) 1984-Kobs, P.S. #14097; Survey L.3705, Pg.116 - Fnd 3/4" Iron Bar in a Monument Box
-) 1993-King, P.S. #30085; Survey L.5831, Pg.303 - Fnd 3/4" Iron Bar in a Monument Box, used same wit as 1984 Survey

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

4-Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 3/4" Iron Rod in a Monument Box 2" below bituminous surface in the centerline of 30 Mile Road, which has a bituminous surface and 14' West of Van Dyke Road, which has a bituminous surface extending to the South & North. No cover on the Monument Box.

Witnesses from LCRC #2, 3 & Survey #2 were used to recover and verify the location of the found 3/4" Iron Rod in a Monument Box.

FIELD MEASUREMENT BETWEEN

I-5 to H-5 2643.30 Feet
I-5 to I-6 2761.82 Feet

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 9-20-94

William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the found 3/4" Iron Rod in a Monument Box with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" in a existing Monument Box.
S49°E 56.08' Set PK & Remon. Washer SW face Power Pole
S51°W 128.97' NE corner of Huntington Bank
N38°E 124.09' Set PK & Remon. Washer NW face Power Pole
N71°W 62.27' Set PK & Remon. Washer South face Power Pole

selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the location of the original corner.



By Huston K. Kennedy
Surveyor's Michigan License No. 17623

Date September 20, 1994