

**SURVEY &
REMONUMENTATION**

C126150

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

94 SEP 30 AM 9:00

For corners in **COMMISSION**
Macomb
(County)

Located In: Washington
Township Corner Code #

CARMILLE BAUGH
REGISTER OF DEEDS
MACOMB COUNTY, MI

- | | | | | | |
|------------------------------------|---|-----------|---|------------|------------|
| 1. Public Land Survey | T | <u>4N</u> | R | <u>12E</u> | <u>I-7</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |

118F **06464PG463**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Huston K. Kennedy, in a field survey on August 21, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	N
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set Post 28" White Oak N37°E 11 Links; 21" White Oak N80°W 24 Links
- 1975-Hooth, P.S. #7966; LCRC L.2643, Pg.102 - Fnd PK Nail
 - 1975-Smith, P.S. #16052; LCRC L.2747, Pg.597 - Fnd 1" Pin in a Monument Box
 - 1986-Avey, P.S. #30076; LCRC L.4080, Pg.890 - Fnd 1" Bar in a Monument Box
 - 1976-Smith, P.S. #16052; Survey L.2747, Pg.596 - Fnd 1" Pin in a Monument Box, used same wit as 1975 LCRC
 - 1978-Kobs, P.S. #14097; Survey L.3021, Pg.148 - Fnd Iron in a Monument Box
 - 1978-Kobs, P.S. #14097; Survey L.3021, Pg.181 - Fnd Iron in a Monument Box, used same wit as 1978 Survey
 - 1979-Kobs, P.S. #14097; Survey L.3074, Pg.519 - Fnd Iron in a Monument Box, used same wit as 1978 Survey
 - 1982-Kobs, P.S. #14097; Survey L.3421, Pg.542 - Fnd Iron Bar in Monument Box, used same wit as 1978 Survey
 - 1982-Kobs, P.S. #14097; Survey L.3421, Pg.543 - Fnd Iron Bar in Monument Box, used same wit as 1978 Survey

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" Copper Rod w/1" Cone Copper Top in a Monument Box in the intersection of 29 Mile Road, which has a bituminous surface, and Van Dyke, which has a bituminous surface.

Witnesses from LCRC #1, 2, 3 & Survey #6 were used to recover and verify the location of the found 1/2" Copper Rod w/1" Cone Copper Top in a Monument Box.

FIELD MEASUREMENT BETWEEN

- I-7 to H-7 2541.45 Feet
- I-7 to I-8 2648.35 Feet
- I-7 to J-7 2646.56 Feet

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1980 AT A MEETING HELD ON 8-30-94

William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-7 I replaced the 1/2" Copper Rod w/1" Cone Copper Top with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" in a existing Monument Box.
- N41°W 52.79' Set PK & Remon. Washer SW face Power Pole
 - N56°E 73.33' Set PK & Remon. Washer NW face Power Pole
 - S67°W 91.04' Set PK & Remon. Washer SE face Power Pole
 - S44°E 58.85' Set PK & Remon. Washer NE face Power Pole

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by Huston K. Kennedy
Surveyor's Michigan License No. 17623

Date SEP 30 1994

