

LIBER 05166 PD 025

B998638

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970.

For corners in

Macomb

(County)

Located In:

Washington Twp.

Corner Code #

I-11

1. Public Land Survey

T 4 R 12

T R

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

4. Lot No. Recorded Plat

5. Private Claims

RECORDED IN MACOMB COUNTY
RECORDED AT 8:30 A.M.

DEC 28 1993

Leonida Young
CLERK - REGISTER OF DEEDS
MACOMB COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

I, Huston K. Kennedy, in a field survey on December 10, 1993

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set post; 18" Ash S80°W 13 Lnks; 10" Ash N37°E 36 Lnks
- 1973 Kobs, P.S. #14097; LCRC L.2360, Pg.814 - Fnd 1/2" Iron Rod in Monument Box.
- 1973 Kobs, P.S. #14097; Survey L.2360, Pg.827 - Same wits as 1973 LCRC
- 1973 Kobs, P.S. #14097; Survey L.2370, Pg.385 - Same wits as 1973 LCRC
- 1992 Money, P.S. #30092; LCRC L.5643, Pg.626 - Fnd 1/2" Iron Rod in Monument Box.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" Iron Rod in a monument box without a cover located in the centerline of 27 Mile Road, which is bituminous surface and 5' West of the center of Jewell Road to the South and 3' West of the center of Jewell road to the North, which is gravel surface North and South.

All witness points from the 1992 LCRC were still existing and they were used to recover and verify the found 1/2" Iron Rod in a monument box.

ACCEPTED BY THE MACOMB COUNTY
SURVEY PEER GROUP AS THE OFFICIAL
CORNER UNDER MICHIGAN PUBLIC ACT 345
OF 1990 AT A MEETING HELD ON
12-15-93

Frank J. DeDecker
FRANK J. DeDECKER, PS, PE, CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

- I-11 I replaced the found 1/2" Iron Rod in a monument box with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" in a monument box.
- N77°E-125.36'-Set PK Nail & Remon. tag above the existing witness in South face Power Pole.
- N40°W-33.26'-Set PK Nail & Remon. tag above the existing witness in East face Power Pole.
- S11°W-117.95'-Set PK Nail & Remon. tag in West face Power Pole.
- N34°W-108.24'-Set PK Nail & Remon. tag in West face 18" Ash.

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.



Signed by *Huston K. Kennedy*
Surveyor's Michigan License No. 17623

Date 12-16-93