

LIBER 06166PG026

R999639

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Macomb (County)

Located In: Washington Twp. Corner Code # I-12

RECORDED IN MACOMB COUNTY
RECORDS AT: 8:30 AM

DEC 28 1993

Carroll A. ...
CLERK - REGISTER OF DEEDS
MACOMB COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 4 R 12 I-12
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. Cell (12, 34) contains a dot.

I, Huston K. Kennedy, in a field survey on December 10, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set post; 11" Maple N68°E 13 Lnks; 9" Maple N89°W 14 Lnks
1976-Kobs, P.S. #14097; Survey L.2747, Pg.926 - Fnd 3/4" Iron Rod in a monument box.
1976-Kobs, P.S. #14097; LCRC L.2747, Pg.936 - Same wits as 1976 Survey
1978-Kobs, P.S. #14097; Survey L.2923, Pg.818 - Same wits as 1976 Survey
1979-Kobs, P.S. #14097; Survey L.3074, Pg.523 - Same wits as 1976 Survey
1990-Avey, P.S. #30076; LCRC L.5014, Pg.016 - Fnd 1/2" Iron Rod
1992-Money, P.S. #30092; LCRC L.5643, Pg.624 - Fnd 1/2" Iron Rod

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" Iron Rod located 3' West of the center of Jewell Road, which is gravel, and 1" under the road surface.

Four witness points from the 1990 LCRC were found and they were used to recover and verify the found 1/2" Iron Rod.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-15-93
FRANK J. DeDECKER, PS, PE, CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-12 I replaced the found 1/2" Iron rod with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" in a monument box.
S87°E-115.97'-Set PK Nail & Remon. tag in North face 13" Cedar.
S37°E-61.92'-Set PK Nail & Remon. tag in NE face 14" Pine.
S89°W-53.59'-Set PK Nail & Remon. tag in North face Power Pole.
N31°W-52.38'-Set PK Nail & Remon. tag above existing witness in West face 11" Ash (w/10" Ash)

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best evidence of the position of the original corner.

Signed by [Signature]
Surveyor's Michigan License No. 17623

Date 12-10-93

