

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Macomb (County)

Located In: Washington Twp. Corner Code # I-13

RECORDED IN MACOMB COUNTY RECORDS AT: 8:30 AM.

DEC 28 1993

Signature of Clerk-Register of Deeds, Macomb County, Michigan

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 4 R 12 I-13
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

- 4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. A dot is marked in row 12, column H.

I, Huston K. Kennedy, in a field survey on December 10, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set post; 10" Sugar Maple S66°W 15 Lnks; 24" Ash N18°W 17 Lnks
1976-Kobs, P.S. #14097; Survey L.2747, Pg.926 - Fnd 3/4" Iron Rod in a monument box.
1976-Kobs, P.S. #14097; LCRC L.2747, Pg.932 - Same wits as 1976 Survey
1978-Kobs, P.S. #14097; Survey L.2923, Pg.818 - Same wits as 1976 Survey
1979-Kobs, P.S. #14097; Survey L.3074, Pg.523 - Same wits as 1976 Survey
1990-Avey, P.S. #30076; LCRC L.5014, Pg.016 - Fnd 3/4" Iron Rod in a monument box.
1992-Honey, P.S. #30092; LCRC L.5643, Pg.626 - Fnd 5/8" Iron Rod in a monument box.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 3/4" Iron Rod in a monument box without a cover that is located 1' South of the centerline of 26 Mile Road, which is bituminous surface, and 9' West of the center of Jewell Road to the North, which is gravel surface. Also, found 3/4" Iron Rod in a monument box 45.80' West of the Section corner. This is the NW corner Section 2 and the NE corner Section 3 for Shelby Township.

All witness points from the 1992 LCRC were found and they were used to recover and verify the found 3/4" Iron Rod in a monument box.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-15-93. Signature of Frank J. DeDecker, PS, PE, CHAIRMAN.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-13 I replaced the found 3/4" Iron Rod in a monument box with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" in a monument box.
N42°E-66.75'-Set PK Nail & Remon. tag above existing witness in SE face Power Pole
S41°E-36.07'-Set PK Nail & Remon. tag above existing witness in SW face 18" Black Walnut
S29°W-37.78'-Set PK Nail & Remon. tag in West face Power Pole
N34°W-38.82'-Set PK Nail & Remon. tag in SW face Power Pole

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature] Surveyor's Michigan License No. 17623

Date 12-10-93

