

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Macomb
 (County)

Located In: Washington Twp
 Corner Code # _____

- | | | |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>4N</u> R <u>12E</u> | <u>J-1</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

SURVEY & REMONUMENTATION

FEB 27 1997

COURT RECORDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Huston K. Kennedy, in a field survey on 4/22, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | | |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

- A. Description of original monument and accessories and/or subsequent restoration:
 1817-GLO Wampler, D.S.; Post not set
 1.) 1979-Verba, PS #13603; LCRC L.3074, Pg.8 - Fnd P.K. Nail
 2.) 1979-Alloway, PS #12043; Survey L.3127, Pg.751 - Fnd P.K. Nail

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 5-21-96
William E. Soderberg
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1996 Kennedy Surveying, Inc. - Kennedy, PS #17623 - The corner was removed and not replaced after the resurfacing of 32 Mile Road which extends to the East & West and has a bituminous surface.

I recovered the corner by using the witnesses from the LCRC recorded in Liber 3074, Page 8 and a Certificate of Survey recorded in Liber 3127, Page 751. The corner is in a line in the West Right-of-Way line of Denby Street which extends to the South. The South 1/4 corner of Section 35, T5N, R12E, Bruce Twp., (J-13) is located 14.06 feet to the West. The corner J-1 was set on a straight line between J-13 to K-13.

Witnesses from LCRC #1 & Survey #2 were used to recover and verify the location of the found corner.

See back side of LCRC

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 J-1 I set a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345" #17623 in a new Monument Box
 N61°W 65.61' Set PK & Remon Washer SW face 13" Maple
 N44°E 45.09' Set PK & Remon Washer SE face 14" Maple
 S55°W 59.90' Set PK & Remon Washer NW face 10" Maple
 S17°W 27.90' Set PK & Remon Washer NW face Power Pole

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature]
 Surveyor's Michigan License No. 17623

Date 12-12-96



J
 9
 590

FIELD MEASUREMENTS BETWEEN

J-1 to I-1 No GLO, 2669.08 Ft. (GPS-MEA)

J-1 to J-13 No GLO, 13.96 Ft., L.3288, Pg.637 & 14.06 Ft. (MEA)

J-1 to K-1 No Glo, 2685.65 Ft., L.3127, Pg.751 & 2685.79 Ft. (GPS-MEA)

C0458181 LIBER:07298 PAGE:213 10:47A 01/02/1997
CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS

SURVEY &
REMONUMENTATION

FEB 27 1997

COMMISSION