

SURVEY & REMONUMENTATION

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE

C126152

94 SEP 30 AM 9:00

For corners in
Macomb **COMMISSION**
(County)

Filing Requirement of Act 74, Mich. P.A. 1970
Washington
Township Corner Code #

CARMELLA BRAGAUGH
REGISTER OF DEEDS
MACOMB COUNTY, MI

1. Public Land Survey	T	4N	R	12E	J-7
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

LIBER 06464P465

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Huston K. Kennedy, in a field survey on August 21, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set Post 5" Ironwood N58°E 19 Links; 11" Maple S43°W 7 Links
- 1.) 1981-Hooth, P.S. #7966; LCRC L.? Pg.? - Fnd 3/4" Iron Pipe
 - 2.) 1978-Kobs, P.S. #14097; Survey L.3021, Pg.148 - Fnd 3/4" Pipe
 - 3.) 1978-Kobs, P.S. #14097; Survey L.3021, Pg.181 - Fnd 3/4" Pipe, used same wit as 1978 Survey
 - 4.) 1982-Kobs, P.S. #14097; Survey L.3421, Pg.542 - Fnd 3/4" Pipe in a Monument Box
 - 5.) 1982-Kobs, P.S. #14097; Survey L.3421, Pg.543 - Fnd 3/4" Pipe in a Monument Box, used same wit as 1982 Survey
 - 6.) 1982-Kobs, P.S. #14097; Survey L.3421, Pg.544 - Fnd 3/4" Pipe in a Monument Box, used same wit as 1982 Survey
 - 7.) 1989-Kobs, P.S. #14097; Survey L.4729, Pg.182 - Fnd 3/4" Pipe

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 3/4" Iron Pipe in a Monument Box centerline of 29 Mile Road, which has a bituminous surface, and a tree-fence row extending to the North & South.

Witnesses from LCRC #1 & 2 were used to recover and verify the location of the found 3/4" Iron Pipe in a Monument Box.

FIELD MEASUREMENT BETWEEN

J-7 to I-7 2646.56 Feet
J-7 to K-7 2725.34 Feet

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 8-30-94.
William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- J-7 I replaced the 3/4" Iron Pipe in a Monument Box with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" in a existing Monument Box.
Due North 31.65' Set PK & Remon. Washer West face Power Pole
Due South 33.78' Set PK & Remon. Washer East face Guide Pole
S56°E 107.15' Set PK & Remon. Washer NE face Power Pole
N72°E 124.91' Set PK & Remon. Washer SE face Power Pole

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by *Huston K. Kennedy*
Surveyor's Michigan License No. 17623

Date AL

