

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

C105009

For corners in

Washington

Macomb
(County)

Located In: Township Corner Code #

1. Public Land Survey	T	4	N	R	12	E	J-9
2. Property Controlling in Section	S						
3. Miscellaneous Property in Sec.	S						

LIBER 06415PC486

94 AUG -5 PM 1:43

CARMEL SABAUGH
REGISTER OF DEEDS
MACOMB COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Huston K. Kennedy, in a field survey on June 15, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-Glo Wampler, D.S.; Se Post; 10" Red Oak N23*W 18 Links; 11" Sugar S62*E 9 Links
- 1.) 1977-Kobs, P.S. #14097; LCRC L.2788, Pg.370 - Fnd 1/2" Pipe
 - 2.) 1978-Kobs, P.S. #14097; LCRC L.3021, Pg.203 - Fnd 3/4" Iron Pipe
 - 3.) 1986-King, P.S. #30085; LCRC L.4055, Pg.682 - Fnd 1/2" Iron Rod
 - 4.) 1977-Kobs, P.S. #14097; Survey L.2788, Pg.384 - Fnd 1/2" Pipe, used same wits as 1977 LCRC
 - 5.) 1978-Avey, P.S. #15396; Survey L.2914, Pg.852 - Fnd 1/2" Pipe, used same wits as 1977 LCRC
 - 6.) 1978-Kobs, P.S. #14097; Survey L.2923, Pg.846 - Fnd 1/2" Pipe, used same wits as 1977 LCRC
 - 7.) 1986-Kobs, P.S. #14097; Survey L.4055, Pg.616 - Fnd 1/2" Iron, used same wits as 1986 LCRC
 - 8.) 1987-Kobs, P.S. #14097; Survey L.4151, Pg. 87 - Fnd 1/2" Pipe, used same wits as 1977 LCRC
 - 9.) 1993-King, P.S. #30085; Survey L.5831, Pg.273 - Fnd 1/2" Iron Bar, used same wits as 1986 LCRC

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" Iron Rod 3' North of the centerline of 28 Mile Road, which has a gravel surface, and a tree-fence row extending to the North & South.

Witnesses from LCRC #1 & 3 were used to recover and verify the location of the found 1/2" Iron Rod.

FIELD MEASUREMENT BETWEEN

J-9 to I-9 2692.43 Feet
J-9 to K-9 2685.86 Feet

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER
GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN
PUBLIC ACT 345 OF 1990 AT A MEETING HELD
ON 7-19-94
William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- J-9 I replaced the found 1/2" Iron Rod with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623".
- N45°E 39.55' Set PK & Remon. Washer NW face 20" Ash
 - N60°E 69.87' Set PK & Remon. Washer South face 24" Maple
 - S50°E 55.30' Set PK & Remon. Washer North face 27" Oak
 - S10°E 33.87' Set PK & Remon. Washer East face 8" Ash

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.



Signed by *Huston K. Kennedy*

Date July 21, 1994

Surveyor's Michigan License No. 17623