

**SURVEY &
REMONUMENTATION**

C105010

APR 28 1995

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in **COMMISSION**
Macomb
(County)

Washington
Located In: Township Corner Code ##

LIBER 06415PG487

94 AUG -5 PM 1:43

CARMELLA SABAUGH
REGISTER OF DEEDS
MACOMB COUNTY, MI

Register of Deeds Stamp & File Number

- | | | |
|------------------------------------|----------------------------|-------------|
| 1. Public Land Survey | T <u>4</u> N R <u>12</u> E | <u>J-11</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Huston K. Kennedy, in a field survey on June 15, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set Post; 14" Oak S38°E 5 Links; 6" Elm N52°W 22 Links
1.) 1989-Dunn, P.S. #30081; LCRC L.4662, Pg.734 - Fnd 1" Spike in a Monument Box
2.) 1992-Money, P.S. #30092; LCRC L.5643, Pg.623 - Fnd Form Pin in a Monument Box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1" Iron Rod in a Monument Box 2.7 feet South of the centerline of 27 Mile Road, which has a bituminous surface, a tree row extending to the North & South.

Witnesses from LCRC's #1 & 2 were used to recover and verify the location of the found 1" Iron Rod in a Monument Box.

FIELD MEASUREMENT BETWEEN

J-11 to K-11 2725.72 Feet
J-11 to I-11 2652.33 Feet

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 7-18-94

William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-11 I replaced the found 1" Iron Rod in a Monument Box with a 3/4" x 24" Iron Rod w/2" diameter aluminum washer stamped Macomb County Monument MI Act 345 #17623 in a existing Monument Box.
S52°W 38.17' Set PK & Remon. Washer North face Power Pole
S70°E 130.49' Set PK & Remon. Washer NE face Power Pole
N46°E 46.18' Set PK & Remon. Washer SE face Power Pole
N12°E 62.46' Set PK & Remon. Washer East face 27" Poplar

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.



Signed by Huston K. Kennedy Date July 21, 1994
Surveyor's Michigan License No. 17623