

LIBER 08166PC028

B999641

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Macomb (County)

Located In: Washington Twp.

Corner Code #

RECORDED IN MACOMB COUNTY
RECORDS AT: 8:30 A.M.

DEC 28 1993

Signature of Clerk-Register of Deeds

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 4 R 12 J-13
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-L and rows 2-13. A dot is marked at row 10, column J.

I, Huston K. Kennedy, in a field survey on December 10, 1993 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set post; 6" Poplar N44°W 11 Lnks; 4" Dogwood S12°E 10 Lnks
1976-Bridges, P.S. #5779; Survey L.2751, Pg.478 - Fnd Iron Rod
1977-Avey, P.S. #15396; Survey L.2886, Pg.957 - Fnd 1" pipe in a monument box.
1978-Kobs, P.S. #14097; Survey L.2923, Pg.818 - Fnd 1" Pipe in a monument box.
1979-Kobs, P.S. #14097; Survey L.3074, Pg.523 - Fnd 1" Pipe in a monument box.
1992-Money, P.S. #30092; LCRC L.5643, Pg.624 - Fnd 1" Pipe in a monument box.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1" Iron Pipe in a monument box that is located 1.5' North of the centerline of 26 Mile Road, which is bituminous surface.

Two witness points from the 1992 LCRC were found and they were used to recover and verify the found 1" Iron Pipe in a monument box.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-15-93
FRANK J. Dedecker, PS, PE, CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

- J-13 I replaced the found 1" Iron Pipe in a monument box with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" in a monument box.
N06°E-123.24'-Set PK Nail & Remon. tag in West face 34" Elm
S62°E-68.05'-Set PK Nail & Remon. tag in NE face Power Pole
S45°W-43.05'-Set PK Nail & Remon. tag in NW face 30" Box Elder
S70°W-90.59'-Set PK Nail & Remon. tag in NW face Power Pole

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature] Date 12-10-93
Surveyor's Michigan License No. 17623

