

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Macomb

(County)

Washington Twp

Located In:

Corner Code #

1. Public Land Survey

T 4N R 12E

K-2

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling  
in Section

S \_\_\_\_\_

T \_\_\_\_\_

R \_\_\_\_\_

S \_\_\_\_\_

T \_\_\_\_\_

R \_\_\_\_\_

3. Miscellaneous  
Property in Sec.

S \_\_\_\_\_

T \_\_\_\_\_

R \_\_\_\_\_

S \_\_\_\_\_

T \_\_\_\_\_

R \_\_\_\_\_

**SURVEY &  
REMONUMENTATION**

FEB 27 1997

**COMMISSION**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Huston K. Kennedy, in a field survey on April 12 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2	●	1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

1817-GLO Wampler, D.S.; Set Post 12" Ironwood N64.5°W 31 Links; 10" Ironwood S82°E 21 Links  
 1.) 1979-Verba, PS #13603, LCRC L.3074, Pg.7 - Fnd 1/2" Iron Bar

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 4-16-96  
*William E. Soderberg*  
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1996 Kennedy Surveying, Inc. - Kennedy, PS #17623 - I used the witnesses from LCRC #1 to set a 3/4" x 24" Iron Rod w/cap 0.4 feet East of a 4" diameter steel fence corner with new woven wire fence extending to the North & West with an old fence line extending to the South & East.

Witnesses from LCRC #1 were used to recover and verify the location of the set 3/4" x 24" Iron Rod w/cap 0.4 feet of fence corner.

FIELD MEASUREMENTS BETWEEN

K-2 to K-1 GLO = 48.17 chains or 3179.22 Ft.  
 K-2 to K-1 3164.12 Ft. (M.D.O.T.), 3158.48 Ft. (GPS-MEA)  
 K-2 to K-3 GLO = 40 chains or 2640.00 Ft.  
 K-2 to K-3 2671.09 Ft. (M.D.O.T.) 2670.70 Ft. (GPS-MEA)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-2 I set a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345" #17623  
 N11°E 31.85' Set PK & Remon Washer West face 10" Elm  
 S71°E 32.37' Set PK & Remon Washer SW face 12" Ash  
 S02°E 20.02' Set PK & Remon Washer East face 12" Maple  
 S45°W 31.89' Set PK & Remon Washer NW face 7" Maple

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by *Huston K. Kennedy*  
 Surveyor's Michigan License No. 17623

Date 12-6-96



626