

# SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

## LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970  
Washington

C126154

94 SEP 30 AM 9:00

CARMEL BAUGH  
REGISTER OF DEEDS  
MACOMB COUNTY, MI

For corners in  
Macomb

(County)

Located In: Washington Township Corner Code #

1. Public Land Survey	T	4N	R	12E	K-8
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

LIBER 06464 PG 467

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Huston K. Kennedy, in a field survey on August 21, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE:** Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1817-GLO Wampler, D.S.; Set Post; 9" Ironwood S67° E 6 Links; 8" Ironwood N20° E 17 Links
- 1.) 1988-Avey, P.S. #15396; LCRC L.4353, Pg.439 - Fnd "T" Bar bent, replaced with 1/2" Bar
  - 2.) 1989-Avey, P.S. #15396; LCRC L.4584, Pg.239 - Fnd 1/2" Bar, used same wit as 1988 LCRC
  - 3.) 1989-Kobs, P.S. #14097; LCRC L.4729, Pg.131 - Fnd 1/2" Iron
  - 4.) 1975-Kobs, P.S. #14097; Survey L.2590, Pg.321 - Fnd "T" Iron
  - 5.) 1987-Kobs, P.S. #14097; Survey L.4220, Pg.474 - Fnd "T" Iron, used same wit as 1975 Survey

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" Iron Rod in the centerline of Schoenherr Road, which has a gravel surface, and a tree row to the West 15' South of driveway for house #62000.

Witnesses from LCRC #1, 3 and Survey #4 were used to recover and verify the location of found 1/2" Iron Rod.

FIELD MEASUREMENT BETWEEN

K-8 to K-7 2541.70 Feet  
K-8 to K-9 2584.27 Feet

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER  
GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN  
PUBLIC ACT 345 OF 1990 AT A MEETING HELD  
ON 8-30-94  
William E. Soderberg  
WILLIAM E. SODERBERG, P.S., CHAIRMAN

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- K-8 I replaced the 1/2" Iron Rod with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623".
- S17° E 149.43' Set PK & Remon. Washer SW face Power Pole
  - N32° E 63.07' Set PK & Remon. Washer NW face Power Pole
  - N78° W 24.24' Set PK & Remon. Washer South face 15" Ash
  - S42° W 45.88' Set PK & Remon. Washer NW face 19" Walnut

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature] Date \_\_\_\_\_  
Surveyor's Michigan License No. 17623

