

SURVEY & REMONUMENTATION

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

C105011

For corners in Macomb (County) COMMISSION Washington Township Located in: Corner Code # ---

LIBER 06415PC488
94 AUG -5 PM 1:43
CAMPBELL BAUGH
REGISTER OF DEEDS
MACOMB COUNTY, MI

- 1. Public Land Survey T 4 N R 12 E K-9
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Huston K. Kennedy, in a field survey on June 15, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1817-GLO Wampler, D.S.; Set Post; 24" Lynn N13°E 21 Links; 8" Lynn S13°W 15 Links
 - 1.) 1972-Kobs, P.S. #14097; LCRC L.2350, Pg.815 - Fnd 3/4" Iron Bar in a Monument Box
 - 2.) 1978-Kobs, P.S. #14097; Survey L.2923, Pg.846 - Same wit as 1972 LCRC
 - 3.) 1984-Kobs, P.S. #14097; Survey L.3579, Pg.134 - Same wit as 1972 LCRC
 - 4.) 1986-Kobs, P.S. #14097; Survey L.4055, Pg.616 - Same wit as 1972 LCRC
 - 5.) 1987-Kobs, P.S. #14097; Survey L.4151, Pg.87 - Same wit as 1972 LCRC

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 3/4" Iron in a Monument Box in the centerline of 28 Mile Road, which is a gravel surface, and 3.7' West of the centerline of Schoenherr, which is a gravel surface.

Witnesses from LCRC #1 were used to recover and verify the location of the found 3/4" Iron in a Monument Box.

FIELD MEASUREMENT BETWEEN
K-9 to J-9 2685.86 Feet
K-9 to K-10 2690.74 Feet

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1980 AT A MEETING HELD ON 7-19-94
William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- K-9 I replaced the found 3/4" Iron in a Monument Box with 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" in an existing Monument Box.
 - S45°E 34.24' Set PK & Remon. Washer SW face Power Pole
 - N45°E 44.58' Set PK & Remon. Washer NW face Power Pole
 - N45°W 43.93' Set PK & Remon. Washer NE face Wooden Fence Post Corner
 - S40°W 89.08' Set PK & Remon. Washer SE face 8" Ash

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.



Signed by Huston K. Kennedy
Surveyor's Michigan License No. 17623

Date July 21, 1994