

SURVEY & REMONUMENTATION

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Washington

C105013

For corners in **COMMISSION**

Macomb
(County)

Located In: Township _____ Corner Code # _____

1. Public Land Survey	T	4	N	R	12	E	K-11
	T		R				
	T		R				
	T		R				
2. Property Controlling in Section	S		T		R		
	S		T		R		
3. Miscellaneous Property in Sec.	S		T		R		
	S		T		R		

LIBER 06415PC490

94 AUG -5 PM 1:43

CARRIE M. BAUGH
REGISTER OF DEEDS
MACOMB COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Huston K. Kennedy, in a field survey on June 15, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set Post; 8" Beech N78°E 14 Links; 12" Beech N17°W 17 Links
- 1.) 1972-Avey, P.S. #15396; LCRC L.2268, Pg.58 - Fnd 3/4" Pipe in a Monument Box
- 2.) 1979-Kobs, P.S. #14097; LCRC L.3162, Pg.604 - Fnd 3/4" Pipe in a Monument Box
- 3.) 1989-Dunn, P.S. #30081; LCRC L.4662, Pg.734 - Fnd 3/4" Pipe in a Monument Box
- 4.) 1992-Money, P.S. #30092; LCRC L.5643, Pg.625 - Fnd 3/4" Pipe in a Monument Box
- 5.) 1971-Avey, P.S. #15396; Survey L.2252, Pg.235 - Same wit as 1972 LCRC
- 6.) 1984-Kobs, P.S. #14097; Survey L.3666, Pg.540 - Same wit as 1979 LCRC

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 3/4" Iron Pipe in a Monument Box in the intersection of the centerline of 27 Mile Road, which has a bituminous surface, and Schoenherr Road, which has a gravel surface.

Witnesses from LCRC #1, 3 & 4 were used to recover and verify the location of the found 3/4" Iron Pipe in a Monument Box.

FIELD MEASUREMENT BETWEEN

- K-11 to K-10 2634.36 Feet
- K-11 to J-11 2725.72 Feet
- K-11 to K-12 2640.29 Feet

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER
GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN
PUBLIC ACT 345 OF 1990 AT A MEETING HELD
ON 7-19-94
William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-11 I replaced the found 3/4" Iron Pipe in a Monument Box with 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" in a existing Monument Box.
- N45°E 49.09' Set PK & Remon. Washer SE face Power Pole
- N80°E 94.85' Set PK & Remon. Washer West face Power Pole
- S47°W 40.82' Set PK & Remon. Washer SE face Power Pole
- N80°W 80.18' Set PK & Remon. Washer SW face 27" Maple

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.



Signed by *Huston Kennedy*
Surveyor's Michigan License No. 17623

Date July 21, 1994