

SURVEY & REMONUMENTATION

C126155

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

94 SEP 30 AM 9:00

For corners in
Macomb **COMMISSION**
(County)

Located In: Washington Township Corner Code ##

CARMEL A. BRAGAUGH
REGISTER OF DEEDS
MACOMB COUNTY, MI

1. Public Land Survey	T	4	N	R	12	E	K-12
	T		R				
	T		R				
	T		R				
2. Property Controlling in Section	S		T		R		
	S		T		R		
3. Miscellaneous Property in Sec.	S		T		R		
	S		T		R		

IBER06464PC468

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Huston K. Kennedy, in a field survey on June 15, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set Post; 11" Beech S52*W 14 Links; 14" Beech S80*E 23 Links
 1.) 1972-Kobs, P.S. #14097; LCRC L.2332, Pg.285 - Fnd 1/2" Square Iron Bar inside a 1" Pipe in a Monument Box
 2.) 1977-Kobs, P.S. #14097; LCRC L.2775, Pg.799 - Fnd 1/2" Square Iron Bar inside a 1" Pipe in a Monument Box
 3.) 1986-King, P.S. #30085; LCRC L.4077, Pg.534 - Fnd 1/2" Square Iron Bar inside a 1" Pipe in a Monument Box
 4.) 1984-Kobs, P.S. #14097; Survey L.3705, Pg.78 - Fnd 1/2" Square Iron Bar inside a 1" Pipe in a Monument Box
 5.) 1989-Kobs, P.S. #14097; Survey L.4621, Pg.512 - Fnd 1/2" Square Iron Bar inside a 1" Pipe in a Monument Box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" Square Iron inside a 1" Iron Pipe in a Monument Box, 2.5' West of the centerline of Schoenherr Road, which has a gravel surface, and a tree row extending to the East and West, also the North line of a Detroit Edison Easement.

Witnesses from LCRC #2 & 3 were used to recover and verify the location of the found 1/2" Square Iron inside a 1" Iron Pipe in a Monument Box.

FIELD MEASUREMENT BETWEEN

K-12 to K-11 2640.29 Feet
K-12 to K-13 2638.18 Feet

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER
GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN
PUBLIC ACT 345 OF 1990 AT A MEETING HELD
ON 8-16-94

William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-12 I replaced the found 1/2" Square Iron inside a 1" Iron Pipe in a Monument Box with 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument" MI Act 345 #17623" in a existing Monument Box.
 N75*W 27.89' Set PK & Remon. Washer SE face 8" Ash
 S80*W 28.40' Set PK & Remon. Washer SE face 4" Ash
 Due East 25.49' Set PK & Remon. Washer South face Power Pole
 N20*E 151.58' Set PK & Remon. Washer West face Power Pole

The selected location is accepted by me and is generally accepted by Professional Surveyors and is the best available evidence of the position of the original corner.

Signed by *Huston K. Kennedy* Date _____
Surveyor's Michigan License No. 17623

