

LIBER 061661029

B999642

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Macomb

(County)

Located In:

Washington Twp.

Corner Code #

K-13

RECORDED IN MACOMB COUNTY RECORDS AT: 8:30 AM

DEC 28 1993

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 4 R 12
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

- 4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-12. A dot is marked at the intersection of column L and row 12.

I, Huston K. Kennedy, in a field survey on December 10, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration: 1817-GLO Wampler, D.S.; Set post; 8" Beech S61°W 10 Lns; 10" Poplar N79°E 19 Lns 1976-Bridges, P.S. #5779; Survey L.2751, Pg.478 - Fnd Iron in a monument box. 1977-Kobs, P.S. #14097; Survey L.2775, Pg.784 - Fnd 5/8" Iron Rod in a monument box. 1977-Kobs, P.S. #14097; Survey L.2882, Pg.428 - Same wits as 1977 Kobs survey 1977-Avey, P.S. #15396; Survey L.2886, Pg.957-958 - Same wits as 1977 Kobs survey 1977-Avey, P.S. #15396; LCRC L.2886, Pg.973 - Same wits as 1977 Avey survey 1978-Avey, P.S. #15396; Survey L.3001, Pg.184 - Same wits as 1977 Avey survey 1992-Money, P.S. #30092; LCRC L.5643, Pg.625 - Fnd 5/8" Iron Rod in a monument box.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: 1993 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 5/8" Iron Rod in a monument box 1.25' South of the centerline of 26 Mile Road, which is bituminous surface, and in the center of Schoenherr Road to the North and 3' West of the center of Schoenherr Road to the South, which is gravel surface North and South.

Two witness points from the 1992 LCRC were found and they were used to recover and verify the found 5/8" Iron Rod in a monument box.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-15-93. FRANK J. DeDECKER, PS, PE, CHAIRMAN

- C. Description of monument for corner and accessories established to perpetuate localizing the position of the corner: K-13 I placed the found 5/8" Iron Rod in a monument box with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" in a monument box. N23°E-125.31'-Set PK Nail & Remon. tag in West face 28" Pine N11°W-152.05'-Set PK Nail & Remon. tag in East face 20" Ash in a clump of 5 Ash S60°W-55.96'-Set PK Nail & Remon. tag above existing witness in NW face Power Pole S45°E-44.15'-Set PK Nail & Remon. tag in SW face Power Pole

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature] Surveyor's Michigan License No. 17623

Date 12-10-93

