

APR 29 1995

COMMISSION

C0210475 LIBER:06660 PAGE:210 12:39P 06/01/1995  
CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Macomb  
(County)

Located In: Washington Corner Code #  
Twp.

- |                                      |             |              |            |
|--------------------------------------|-------------|--------------|------------|
| 1. Public Land Survey                | T <u>4N</u> | R <u>12E</u> | <u>L-5</u> |
|                                      | T _____     | R _____      | _____      |
|                                      | T _____     | R _____      | _____      |
|                                      | T _____     | R _____      | _____      |
| 2. Property Controlling in Section   | S _____     | T _____      | R _____    |
|                                      | S _____     | T _____      | R _____    |
| 3. Miscellaneous Property in Section | S _____     | T _____      | R _____    |
|                                      | S _____     | T _____      | R _____    |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Huston K. Kennedy, in a field survey on April 28, 19 L-5, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set Post 17" Ash S47°E 9 Links; 12" Red Oak S76°W 13 Links
- 1986-King, PS #30085; LCRC L.4077, Pg.538 - Fnd 1/2" Iron w/cap #30085
  - 1992-Donnelly, PS #21563; LCRC L.5298, Pg.946 - Fnd Iron & cap
  - 1974-Kobs, PS #14097; Survey L. 2466, Pg.724 - Fnd 1/2" Iron Bar.
  - 1974-Kobs, PS #14097; Survey L.2474, Pg.836 - Fnd 1/2" Iron Bar, used same wit as (3) 1974 Survey
  - 1975-Kobs, PS #14097; Survey L.2624, Pg.414 - Fnd 1/2" Iron Bar, used same wit as (3) 1974 Survey
  - 1977-Kobs, PS #14097; Survey L.2762, Pg.28 - Fnd 1/2" Iron Bar, used same wit as (3) 1974 Survey
  - 1979-Kobs, PS #14097; Survey L.3162, Pg.609 - Fnd 1/2" Iron Bar, used same wit as (3) 1974 Survey
  - 1986-Kobs, PS #14097; Survey L.4077, Pg.556 - Fnd 1/2" Iron Bar w/cap #30085, used same wit as 1986 LCRC
  - 1988-Kobs, PS #14097; Survey L.4021, Pg.514 - Fnd 1/2" Iron Bar w/cap #30085, used same wit as 1986 LCRC

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd 1/2" Iron Rod w/cap in the centerline of 30 Mile Road, which has a gravel surface extending to the East & West, also a tree row extending to the North & South. Driveway for house #14400 is just South of the corner, also driveway for house #14411 is 36 feet West of the corner.

Witnesses from LCRC #1 and Survey #3 were used to recover and verify the location of the found 1/2" Iron Rod w/cap.

FIELD MEASUREMENTS BETWEEN

L-5 to K-5 2734.00 Ft. GLO = 39.72 chains or 2621.52 Ft.  
L-5 to M-5 2634.58 Ft. GLO = 39.72 chains or 2621.52 Ft.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON MAY 23, 1995.

*William E. Soderberg*  
WILLIAM E. SODERBERG, P.S., CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-5 I replaced the found 1/2" Iron Rod with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623"
- Due North 29.12' Set PK & Remon. Washer West face 21" Locust  
N30°W 32.26' Set PK & Remon. Washer SW face 7" Locust  
N38°W 46.35' Set PK & Remon. Washer SW face 25" Locust  
N63°W 85.46' Set PK & Remon. Washer SW face 29" Locust

The selected location is accepted by me and is generally accepted by Professional Surveyors as the position of the original corner.



Signed by Huston K. Kennedy  
Surveyor's Michigan License No. 17623

Date May 24, 1995