

SURVEY & REMONUMENTATION

APR 29 1996

COMMISSION

C0212000 LIBER:06663 PAGE:857 12:21P 06/06/1995
 CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS
LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Macomb
 (County)

Located In: Washington Corner Code #
Twp.

- | | | | |
|--------------------------------------|-------------|--------------|------------|
| 1. Public Land Survey | T <u>4N</u> | R <u>12E</u> | <u>L-7</u> |
| | T _____ | R _____ | _____ |
| | T _____ | R _____ | _____ |
| | T _____ | R _____ | _____ |
| 2. Property Controlling in Section | S _____ | T _____ | R _____ |
| | S _____ | T _____ | R _____ |
| 3. Miscellaneous Property in Section | S _____ | T _____ | R _____ |
| | S _____ | T _____ | R _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Huston K. Kennedy, in a field survey on April 28, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set Post 14" Ash N43°W 8 Links; 9" Ash S16°W 9 Links
 1.) 1972-Kobs, PS #14097; LCRC L.2262, Pg.620 - Fnd 1/2" Iron Bar
 2.) 1988-Avey, PS #15396; LCRC L.4353, Pg.439 - Fnd 1/2" Bar
 3.) 1989-Avey, PS #15396; LCRC L.4584, Pg.239 - Fnd 1/2" Iron Bar, used same wit as 1988 LCRC
 3.) 1993-King, PS #30085; LCRC L.5778, Pg.410 - Fnd 1/2" Iron w/cap #30085
 4.) 1972-Kobs, PS #14097; Survey L.2262, Pg.618 - Fnd 1/2" Iron Bar, used same wit as 1972 LCRC
 5.) 1989-Kobs, PS #14097; Survey L.4729, Pg.141 - Fnd 1/2" Iron Bar
 6.) 1989-Kobs, PS #14097; Survey L.4729, Pg.158 - Fnd 1/2" Iron Bar, used same wit as 1989 Survey
 7.) 1969-Soderberg; Unrecorded Witnesses - Fnd 5/8" Rerod (Macomb County Road Commission)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd 1/2" Iron Rod w/cap #30085 7.50 feet South of the centerline of 29 Mile Road, which has a bituminous surface extending to the East & West. A tree-fence row extending to the South; and 31 feet of driveway for house #14468.

Witnesses from LCRC #1, 2 & 4 were used to recover and verify the location of the found 1/2" Iron Rod w/cap #30085.

FIELD MEASUREMENTS BETWEEN

L-7 to K-7 2644.67 Ft., GLO = 39.86 chains or 2630.76 Ft.
 L-7 to M-7 2662.08 Ft., GLO = 39.86 chains or 2630.76 Ft.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 5-23-95

William E. Soderberg
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-7 I replaced the found 1/2" Iron Rod with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" setting a new Monument Box.
 N52°W 71.87' Set PK & Remon. Washer SW face Power Pole
 N64°E 95.04' Set PK & Remon. Washer SE face Power Pole
 S03°W 33.54' Set PK & Remon. Washer East face 7" Oak
 S43°W 63.67' Set PK & Remon. Washer NW face 9" Elm

The selected location is accepted by me and is generally accepted by Professional Surveyors as the evidence of the position of the original corner.

Signed by *Huston K. Kennedy*
 Surveyor's Michigan License No. 17623

Date 5/30/95

