

APR 29 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Macomb Located In: Washington Corner Code #
(County) Twp.

- 1. Public Land Survey T 4N R 12E L-9
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Section S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5		4		3		2		1		
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Huston K. Kennedy, in a field survey on April 28, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set Post 17" Ash S17°E 19 Links; 11" Beech N48°E 19 Links
- 1.) 1972-Kobs, PS #14097; LCRC L.2350, Pg.807 - Fnd 1/2" Iron Bar in a Monument Box
- 2.) 1993-Kobs, PS #14097; Survey L.5831, Pg.281 - Fnd 1/2" Iron Bar in a Monument Box, used same wit as 1972 LCRC
- 3.) 1971-Soderberg; Unrecorded Witnesses - Fnd Re-rod
- 4.) 1993-Northeast Survey & Associates, Inc. Unrecorded Survey - Fnd Iron w/cap #14097

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd 1/2" Iron Rod in a Monument Box in the centerline of 30 Mile Road extending to the East & West, which has a gravel surface with a tree row extending to the North.

Witnesses from LCRC #1 were used to recover and verify the location of the found 1/2" Iron Rod in a Monument Box.

FIELD MEASUREMENTS BETWEEN

L-9 to M-9 2640.38 Ft., GLO = 40.02 chains or 2641.32 Ft.
L-9 to K-9 2606.90 Ft., GLO = 40.02 chains or 2641.32 Ft.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 5-23-95
William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-9 I replaced the found 1/2" Iron Rod with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" in a existing Monument Box.
- N09°W 29.85' Set PK & Remon. Washer South face Power Pole
- N23°E 82.55' Set PK & Remon. Washer SE face 22" Hickory
- N62°E 89.40' Set PK & Remon. Washer SE face 25" Maple
- N66°E 103.95' Set PK & Remon. Washer SE face 19" Maple

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature]
Surveyor's Michigan License No. 17623

Date May 24, 1995

