

APR 29 1996

COMMISSION

00212002 LIBER:06663 PAGE:859 12:21P 06/06/1995
 CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Macomb
 (County)

Located In: Washington Corner Code #
Twp.

- | | | | | | | |
|--------------------------------------|---|-----------|---|------------|------------|-------|
| 1. Public Land Survey | T | <u>4N</u> | R | <u>12E</u> | <u>M-6</u> | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| 2. Property Controlling in Section | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |
| 3. Miscellaneous Property in Section | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Huston K. Kennedy, in a field survey on April 28, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set Post 3" Ash N10°E 18 Links; 8" Elm S74°W 20 Links
 1.) 1974-Kobs, PS #14097; Survey L.2466, Pg.724 - Fnd 1/2" Iron Bar at anchor post
 2.) 1979-Kobs, PS #14097; Survey L.3162, Pg.609 - Fnd 1/2" Iron Bar

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd 1/2" Iron Rod 4" below surface at a 3-way fence corner, with a fence-tree row extending to the West, North & South, and 20 feet West of the centerline of the Healy Drain. The West 1/4 corner of Section 18, T4N, R13E, Ray Township (A-6) is located 70.83 feet to the South.

Witnesses from Survey #1 & 2 were used to recover and verify the location of the found 1/2" Iron Rod.

FIELD MEASUREMENTS BETWEEN

- M-6 to M-5 2721.64 Ft. GLO = 40 chains or 2640.00 Ft.
 M-6 to M-7 2708.88 Ft. GLO = 40 chains or 2640.00 Ft.
 M-6 to A-6 (Ray Twp.) 70.83 Ft. to the South

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 5-23-95

William E. Soderberg
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-6 I replaced the found 1/2" Iron Rod with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623"
 N30°E 41.44' Set PK & Remon. Washer SE face 6" Box Elder
 S80°E 34.28' Set PK & Remon. Washer North face 8" Ash
 S50°W 18.41' Set PK & Remon. Washer North face 18" Ash
 Due West 29.30' Set PK & Remon. Washer North face 16" Ash
 South 70.83 Ft. West 1/4 corner of Section 18, T4N, R13E, Ray Township

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by Huston K. Kennedy
 Surveyor's Michigan License No. 17623

Date May 30,

