

SURVEY & REMONUMENTATION

APR 29 1996

COMMISSION

C0212003 LIBER:06663 PAGE:860 12:21P 06/06/1995
 CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Macomb (County) Located in: Washington Twp. Corner Code #

- | | | | |
|--------------------------------------|-------------|--------------|------------|
| 1. Public Land Survey | T <u>4N</u> | R <u>12E</u> | <u>M-7</u> |
| | T _____ | R _____ | _____ |
| | T _____ | R _____ | _____ |
| | T _____ | R _____ | _____ |
| 2. Property Controlling in Section | S _____ | T _____ | R _____ |
| | S _____ | T _____ | R _____ |
| 3. Miscellaneous Property in Section | S _____ | T _____ | R _____ |
| | S _____ | T _____ | R _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Huston K. Kennedy, in a field survey on April 28, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 1817-GLO Wampler, D.S.; Set Post 24" Sugar North 7 Links; 6" Ash N85°E 12 Links
 1.) 1972-Kobs, PS #14097; LCRC L.2262, Pg.622 - Fnd 1" Pipe.
 2.) 1989-Kobs, PS #14097; Survey L.4729, Pg.141 - Fnd 1" Pipe, used same wit as 1972 LCRC

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1995 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd 1" Iron Pipe 2" deep and 75 feet North of the centerline of 29 Mile Road extending to the East & West, which has a bituminous surface with a tree row extending to the North. Corner common to Sections 18 & 19, T4N, R13E, Ray Township (A-7) is located 74.95 feet to the South.

Witnesses from LCRC #1 were used to recover and verify the location of the found 1" Iron Pipe.

FIELD MEASUREMENTS BETWEEN

- M-7 to M-6 2708.88 Ft., GLO = 40.00 chains or 2640.00 Ft.
- M-7 to L-7 2662.08 Ft., GLO = 39.86 chains or 2630.76 Ft.
- M-7 to A-7 (Ray Twp.) 74.95 Ft. to the South, GLO 94 links or 62.04 Ft.
- M-7 to M-8 2719.71 Ft., GLO = 40.00 chains or 2640.00 Ft.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 5-23-95
William E. Soderberg
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 M-7 I replaced the found 1" Iron Pipe with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623"
 N45°W 38.38' NE corner of house #15181
 S06°W 44.00' Set PK & Remon. Washer West face Power Pole
 S40°W 46.55' Set PK & Remon. Washer SE face 29" Maple
 S60°W 70.03' Set PK & Remon. Washer NW face 34" Elm
 South 74.95' corner common to Sections 18 & 19, T4N, R13E, Ray Township (A-7)

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature]
 Surveyor's Michigan License No. 17623

Date May 30, 1995

