

APR 29 1996

COMMISSION 00212004 LIBER:06663 PAGE:861 12:21P 06/06/1995
CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Macomb
(County)

Located In: Washington Corner Code #
Twp.

- 1. Public Land Survey T 4N R 12E M-9
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Section S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Huston K. Kennedy, in a field survey on April 28, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set Post 24" Black Ash N56°W 12 Links; 7" Black Ash N89°W 17 Links
- 1.) 1972-Kobs, PS #14097; LCRC L.2350, Pg.811 - Fnd 1/2" Iron Bar in a Monument Box
- 2.) 1989-Kobs, PS #14097; Survey L.4729, Pg.158 - Fnd 1/2" Iron Bar in a Monument Box, used same wit as 1972 LCRC
- 3.) 1993-King, PS #30085; Survey L.5831, Pg.281 - Fnd 1/2" Iron Bar w/cap #14097 in a Monument Box, used same wit as 1972 LCRC
- 4.) 1993-Northeast Survey & Associates; Unrecorded Survey - Fnd Iron w/cap #14097

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd 1/2" Iron Rod w/cap #14097 in a Monument Box 3" deep 13 feet North of the centerline of 28 Mile Road extending to the East & West, which has a gravel surface and 3 feet West of Hayes Road extending to the South, which has a gravel surface with a tree row extending to the North. The corner common to Sections 19 & 30 T4N, R13E, Ray Township, (A-9) is located 32.70 feet to the South.

Witnesses from LCRC #1 were used to recover and verify the location of the found 1/2" Iron Rod w/cap #14097 in a Monument Box.

FIELD MEASUREMENTS BETWEEN

- M-9 to M-8 2735.83 Ft., GLO = 40.00 chains or 2640.00 Ft.
- M-9 to M-10 2661.61 Ft., GLO = 40.00 chains or 2640.00 Ft.
- M-9 to L-9 2640.34 Ft., GLO = 40.02 chains or 2641.32 Ft.
- M-9 to A-9 (Ray Twp.) 32.70 Ft., GLO = 96.00 links or 63.36 Ft.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 5-23-95
William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-9 I replaced the found 1/2" Iron Rod w/cap #14097 with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" in a existing Monument Box
- N17°W 31.76' Set PK & Remon. Washer East face Power Pole
- S42°E 63.30' Chisled cross in big rock
- S21°W 93.10' Set PK & Remon. Washer East face 29" Poplar
- S67°W 76.05' Set PK & Remon. Washer NW face 6" Poplar
- South 32.70' corner common to Sections 19 & 30, T4N, R13E, Ray Township (A-9)

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by Huston K. Kennedy
Surveyor's Michigan License No. 17623

Date May 30, 1995

