

APR 29 1995

COMMISSION

C0210478 LIBER:06660 PAGE:213 12:39P 06/01/1995
CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Macomb (County) Located In: Washington Corner Code # _____
Twp.

- 1. Public Land Survey T 4N R 12E M-10
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
In Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Section S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Huston K. Kennedy, in a field survey on April 28, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set Post 14" Sugar Tree N54°W 10 Links; 7" Beech S22°W 12 Links
- 1.) 1972-Smith, PS #16052; LCRC L.2314, Pg.675 - Fnd Tee Iron
- 2.) 1972-Kobs, PS #14097; LCRC L.2350, Pg.809 - Fnd Tee Iron w/cap #5787
- 3.) 1972-Smith, PS #16052; Survey L.2314, Pg.668 - Fnd Tee Iron w/cap #5787, used same wit as 1972 LCRC
- 4.) 1975-Barnes, PS #13616; Survey L.2572, Pg.494 - Fnd 1/2" Iron Rod
- 5.) 1976-Kobs, PS #14097; Survey L.2747, Pg.915 - Fnd Tee Iron, used same wit as 1972 LCRC
- 6.) 1978-Kobs, PS #14097; Survey L.3021, Pg.193 - Fnd Tee Iron, used same wit as 1972 LCRC
- 7.) 1979-Smith, PS #16052; Survey L.3184, Pg.661 - Fnd Tee Iron
- 8.) 1986-Kobs, PS #14097; Survey L.4055, Pg.623 - Fnd Tee Iron w/cap #5787, used same wit as 1972 LCRC

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd "T" Iron 5" deep in the centerline of Hayes Road extending to the East & West, which has a gravel surface with a tree row extending to the West, and North 49 feet to driveway for house #60020. The West 1/4 corner of Section 30, T4N, R13E, Ray Township, (A-10) is located 68.50 feet to the South.

Witnesses from LCRC #1 & 2 were used to recover and verify the location of the found "T" Iron.

FIELD MEASUREMENTS BETWEEN

- M-10 to M-9 2661.61 Ft., GLO = 40.00 chains or 2640.00 Ft.
- M-10 to M-11 2697.92 Ft., GLO = 40.00 chains or 2640.00 Ft.
- M-10 to A-10 (Ray Twp.) 68.50 Ft.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 5-23-95

William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-10 I replaced the "T" Iron with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623"
S71°W 25.25' Set PK & Remon. Washer NW face 9" Poplar
S74°W 30.15' Set PK & Remon. Washer SE face 16" Poplar
Due East 89.20' NW corner of house #60020
S49°E 105.75' SW corner of house #60020
South 68.50' the West 1/4 corner of Section 30, T4N, R13E, Ray Township (A-10)

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available position of the original corner.



Signed by [Signature]
Surveyor's Michigan License No. 17623

Date May 24, 1995