

SURVEY & REMONUMENTATION

APR 29 1995 0212005 LIBER:06663 PAGE:862 12:21P 06/06/1995
 CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS
COMMISSION **LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Macomb (County) Located in: Washington Twp. Corner Code # _____

1. Public Land Survey	T	<u>4N</u>	R	<u>12E</u>	<u>M-11</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	R
	S	_____	T	_____	R
3. Miscellaneous Property in Section	S	_____	T	_____	R
	S	_____	T	_____	R

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Huston K. Kennedy, in a field survey on April 28, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 1817-GLO Wampler, D.S.; Set Post 4" White Oak N22°E 12 Links; 3" Ironwood N88°W 8 Links
 1.) 1972-Smith, PS #16052; LCRC L.2314, Pg.675 - Fnd Iron in a Monument Box
 2.) 1976-Kobs, PS #14097; LCRC L.2747, Pg.938 - Fnd 3/4" Iron Bar in a Monument Box
 3.) 1972-Smith, PS #16052; Survey L.2314, Pg.668 - Fnd Iron in a Monument Box, used same wit as 1972 LCRC
 4.) 1976-Kobs, PS #14097; Survey L.2747, Pg.915 - Fnd 3/4" Iron Bar in a Monument Box, used same wit as 1976 LCRC
 5.) 1978-Kobs, PS #14097; Survey L.3021, Pg.159 - Fnd 3/4" Iron Bar in a Monument Box, used same wit as 1976 LCRC
 6.) 1978-Kobs, PS #14097; Survey L.3021, Pg.193 - Fnd 3/4" Iron Bar in a Monument Box, used same wit as 1976 LCRC
 7.) 1979-Smith, PS #16052; Survey L.3184, Pg.661 - Fnd Iron in a Monument Box
 8.) 1986-Kobs, PS #14097; Survey L.4055, Pg.662 - Fnd 3/4" Iron Bar in a Monument Box, used same wit as 1976 LCRC
 9.) 1986-Kobs, PS #14097; Survey L.4055, Pg.663 - Fnd 3/4" Iron Bar in a Monument Box, used same wit as 1976 LCRC

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1995 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd 5/8" Iron Bar in a Monument Box, 3 feet West of the centerline of Hayes Road extending to the North, which has a gravel surface, 46 feet North of the centerline of 27 Mile Road extending to the East & West, which has a bituminous surface a tree row extending to the South. The corner common to Sections 30 & 31, T4N, R11E, Ray Township, (A-11) is located 62.62 feet to the South.

Witnesses from LCRC #1 & 2 were used to recover and verify the location of the found 5/8" Iron Bar in a Monument Box.

FIELD MEASUREMENTS BETWEEN

- M-11 to M-10 2697.92 Ft., GLO = 40 chains or 2640.00 Ft.
- M-11 to M-12 2711.93 Ft., GLO = 40 chains or 2640.00 Ft.
- M-11 to A-11 (Ray Twp.) 62.62 Ft. to the South, GLO = 95 links or 62.70 Ft.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 5-27-95
William E. Soderberg
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 M-11 I replaced the found 5/8" Iron Bar with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" in a existing Monument Box.
 N67°W 44.24' Set PK & Remon. Washer NE face Power Pole
 N87°W 199.99' Set PK & Remon. Washer South face Power Pole
 S15°E 90.21' Set PK & Remon. Washer East face Power Pole
 S63°E 34.39' Set PK & Remon. Washer NE face Power Pole
 South 62.62 Ft. corner common to Sections 30 & 31, T4N, R11E, Ray Twp. (A-11)

The selected location is accepted by me and is generally accepted by Professional Surveyors as the position of the original corner.

Signed by *Huston K. Kennedy*
 Surveyor's Michigan License No. 17623

Date May 30, 1995
 FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, REVISED JAN, 1983

