

SURVEY & REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FEB 27 1997

COMMISSION

For corners in

Macomb
(County)

Located In: Ray Twp Corner Code #

1. Public Land Survey	T <u>4</u> N	R <u>13</u> E	<u>A-4</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

Huston K. Kennedy, in a field survey on April 12, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1817-GLO Wampler, D.S.; Post not set - No Witnesses Trees
1.) 1986-Kobs, PS #14097; Survey L.3880, Pg.84 - Fnd 1/2" Pipe at Anchor Post

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 4-12-96

William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1996 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd 1/2" Iron Pipe 3" above the surface at the base of old 3-way fence corner with a fence-tree line extending to the North, South & East. The East 1/4 corner of Section 12, T4N, R12E, Washington Twp., (M-4) is located 58.98 feet to the North.

Witnesses from Survey #1 were used to recover and verify the location of the found 1/2" Iron Pipe. The corner was set 0.28 feet to the East on a straight line between M-4 to M-5.

FIELD MEASUREMENTS BETWEEN

A-4 to M-4 58.98 Ft. L.3880, Pg.84
A-4 to A-3 No GLO, 2714.98 Ft. L.3880, Pg.84, 2715.27 Ft. (GPS-MEA)
A-4 to A-5 No GLO, 2710.57 Ft. (GPS-MEA)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-4 I set a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345" #17623 0.28 feet East of the found 1/2" Iron Pipe
Due South 81.15' Set PK & Remon Washer East face 19" Ash
Due East 154.15' Set PK & Remon Washer North face 10" Ash
Due North 125.88' Set PK & Remon Washer East face 9" Ash
N86°W 272.94' Set PK & Remon Washer SW face 28" Oak
North 58.98 feet East 1/4 corner Section 12, T4N, R12E, Washington Twp., (M-4)

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by _____
Surveyor's Michigan License No. 17623

Date 12-6-96



619