

SURVEY & REMONUMENTATION

C0214640 LIBER:06670 PAGE:218 10:16A 06/13/1995
 CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS

APR 29 1996

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

corners in
Macomb
 (County)

Located In: Ray Twp. Corner Code # _____

Public Land Survey	T	<u>4N</u>	R	<u>13E</u>	<u>A-5</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
Property Controlling in Section	S	_____	T	_____	R
	S	_____	T	_____	R
Miscellaneous Property in Section	S	_____	T	_____	R
	S	_____	T	_____	R

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
 Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Huston K. Kennedy, in a field survey on April 26, 19 95, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current annual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found or expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

- 1. 817-GLO Preston, D.S.; Set Post 12" Beech S87°E 10 Links; 10" Elm S74°W 19 Links
- 2. 1975-Kobs, PS #14097; LCRC L.2590, Pg.350 - Fnd 1/2" Iron Bar
- 3. 1975-Kobs, PS #14097; Survey L.2590, Pg.322 - Fnd 1/2" Iron Bar, used same wit as 1975 LCRC
- 4. 1981-Kobs, PS #14097; Survey L.3355, Pg.478 - Fnd 1/2" Iron Bar, used same wit as 1975 LCRC
- 5. 1987-King, PS #30085; Survey L.4220, Pg.439 - Fnd 1/2" Iron Bar

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd 1/2" Iron Bar 3" deep 2.50 feet North of the centerline of 30 Mile Road extending to the East & West with a gravel surface, 70 feet West of driveway for house #15261 with a tree, fence & rock row extending to the North & South of the corner. The corner common to Sections 12 & 13, T4N, R12E, Washington Township is located 76.29 feet to the North. (M-5)

Witnesses from LCRC #1 & Survey #3 were used to recover and verify the location of the found 1/2" Iron Bar.

FIELD MEASUREMENTS BETWEEN

- A-5 to M-5 (Washington Twp.) 76.29 Ft., = GLO 1.11 chains or 73.26 Ft.
- A-5 to A-6 2716.25 Ft.
- A-5 to M-6 (Washington Twp.) 2645.35 Ft. to the North

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 5-23-95

William E. Soderberg
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-5 I set a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" on the township line 0.31 feet West of the found 1/2" Iron Bar.
 Due North 38.16' Set PK & Remon. Washer East face 23" Elm
 N37°E 40.22' Set PK & Remon. Washer SE face 11" Ash
 S17°W 29.00' Set PK & Remon. Washer East face Guide Pole
 S53°E 49.75' Set PK & Remon. Washer NE face 14" Elm
 North 76.29 Ft. corner common to Sections 12 & 13, T4N, R12E, Washington Township

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Surveyed by [Signature]
 Surveyor's Michigan License No. 17623

Date June 1, 1995

