

SURVEY & REMONUMENTATION

APR 29 1996

COMMISSION

C0211998 LIBER:06663 PAGE:855 12:21P 06/06/1995
 CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Macomb Located in: Ray Twp. Corner Code # _____
(County)

- | | | | | | |
|--------------------------------------|---|----|---|-----|-----|
| 1. Public Land Survey | T | 4N | R | 13E | A-6 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | T | R | | |
| | S | T | R | | |
| 3. Miscellaneous Property in Section | S | T | R | | |
| | S | T | R | | |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Huston K. Kennedy, in a field survey on April 28, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Preston, D.S.; Post was not set
 1.) 1987-King, PS #30085; Survey L.4220, Pg.439 - Fnd 1/2" Iron Bar

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd 1/2" Iron Rod 2" above surface 75 feet West of the centerline of the Healy Drain, with a fence row extending to the East, and a tree-fence row extending to the North & South. The East 1/4 corner of Section 13, T4N, R12E, Washington Township (M-6) is located 70.83 feet to the North with a fence line extending to the West.

Witnesses from Survey #1 were used to recover and verify the location of the found 1/2" Iron Rod.

FIELD MEASUREMENTS BETWEEN

- A-6 to A-7 2713.08 Ft.
 A-6 to A-5 2716.25 Ft.
 A-6 to M-6 (Washington Twp.) 70.83 Ft. to the North

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 5-23-95

William E. Soderberg
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-6 I set a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" on the township line 0.81 feet East of the found 1/2" Iron Rod.
 N75°E 11.50' Set PK & Remon. Washer North face 10" Ash
 Due West 17.34' Set PK & Remon. Washer North face 12" Maple
 S60°W 28.80' Set PK & Remon. Washer South face 10" Ash
 S40°E 26.98' Set PK & Remon. Washer West face 14" Ash
 North 70.83' East 1/4 corner Section 13, T4N, R12E, Washington Township

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by *Huston K. Kennedy*
 Surveyor's Michigan License No. 17623

Date June 5, 1995

