

**SURVEY & REMONUMENTATION.**

APR 29 1996

C0214641 LIBER:06670 PAGE:219 10:16A 06/13/1995  
CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Macomb  
(County)

Located In: Ray Twp. Corner Code #

- |                                      |                          |            |
|--------------------------------------|--------------------------|------------|
| 1. Public Land Survey                | T <u>4N</u> R <u>13E</u> | <u>A-7</u> |
|                                      | T _____ R _____          | _____      |
|                                      | T _____ R _____          | _____      |
|                                      | T _____ R _____          | _____      |
| 2. Property Controlling in Section   | S _____ T _____ R _____  | _____      |
|                                      | S _____ T _____ R _____  | _____      |
| 3. Miscellaneous Property in Section | S _____ T _____ R _____  | _____      |
|                                      | S _____ T _____ R _____  | _____      |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Huston K. Kennedy, in a field survey on April 26, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

1817-GLO Preston, D.S.; Set Post - No witnesses trees  
1.) 1972-Kobs, PS #14097; LCRC L.2262, Pg.626 - Fnd 1" Iron Bar

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

1995 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd 1" Iron Bar 1 foot North of the centerline of 29 Mile Road extending East & West, which has a bituminous surface, and a tree row extending to the North. The corner common to Sections 13 & 24, T4N, R12E, Washington Township (M-7) is located 74.95 feet to the North.

Witnesses from LCRC #1 were used to recover and verify the location of the found 1" Iron Bar.

**FIELD MEASUREMENTS BETWEEN**

A-7 to A-6 2713.08 Ft.  
A-7 to M-7 (Washington Twp.) 74.95 Ft. to the North, GLO = 94 links or 62.04 Ft.  
A-7 to A-8 2702.47 Ft.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 5-23-95.

*William E. Soderberg*  
WILLIAM E. SODERBERG, P.S., CHAIRMAN

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

A-7 I set a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" on the township line 0.78 feet West of the found 1" Iron Bar setting in a new Monument Box.  
N82°E 134.78' Set PK & Remon. Washer North face Power Pole  
N16°W 35.80' Set PK & Remon. Washer West face Power Pole  
N39°W 59.95' Set PK & Remon. Washer SW face 29" Maple  
S84°W 140.88' Set PK & Remon. Washer North face 17" Elm  
North 74.95' corner common to Sections 13 & 24, T4N, R12E, Washington Township (M-7)

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by *Huston K. Kennedy*  
Surveyor's Michigan License No. 17623

Date June 1, 1995

