

APR 29 1996

C0214642 LIBER:06670 PAGE:220-10:16A-06/13/1995 CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Macomb (County) Located In: Ray Twp. Corner Code #

- 1. Public Land Survey T 4N R 13E A-8
2. Property Controlling in Section S T R
3. Miscellaneous Property in Section S T R
4. Lot No. Recorded Plat
5. Private Claims

Register of Deeds Stamp & File Number

Grid table with columns A-L and rows 2-13. Cell (19, 20) is marked with a dot.

I, Huston K. Kennedy, in a field survey on April 26, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1817-GLO Preston, D.S.; Post was not set
1.) 1972-Kobs, PS #14097; LCRC L.2262, Pg.628 - Fnd 1/2" Iron Bar

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd 1/2" Iron Rod 3" above ground at a four way fence corner extending to the North, South, East & West. The East 1/4 corner of Section 24, T4N, R12E, Washington Township (M-8) is located 57.70 feet to the North.

Witnesses from LCRC #1 were used to recover and verify the location of the found 1/2" Iron Rod.

FIELD MEASUREMENTS BETWEEN

A-8 to A-7 2702.47 Ft.
A-8 to A-9 2710.83 Ft.
A-8 to M-8 (Washington Twp.) 57.70 Ft. to the North

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 5-23-95

Signature of William E. Soderberg, P.S., CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-8 I set a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" on the township line 1.02 feet East of the found 1/2" Iron Rod.
N02°E 12.61' Set PK & Remon. Washer West face 22" Maple
S87°E 7.54' Set PK & Remon. Washer South face 11" Hickory
N57°W 21.59' Set PK & Remon. Washer NE face 13" Maple
S03°W 11.84' Set PK & Remon. Washer West face 10" Hickory
North 57.70' East 1/4 corner of Section 24, T4N, R12E, Washington Township (M-8)

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence position of the original corner.

Signed by [Signature] Date June 1, 1995
Surveyor's Michigan License No. 17623

