

SURVEY & REMONUMENTATION

C0214643 LIBER:06670 PAGE:221 10:16A 06/13/1995
 CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS

APR 29 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Macomb (County) Located In: Ray Twp. Corner Code # _____

- | | | | | | |
|--------------------------------------|---|-----------|---|------------|------------|
| 1. Public Land Survey | T | <u>4N</u> | R | <u>13E</u> | <u>A-9</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |
| 3. Miscellaneous Property in Section | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |
4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Huston K. Kennedy, in a field survey on April 26, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Preston, D.S.; Set Post 18" Ash S04°W 17 Links; 14" Elm N78°E 15 Links
 1.) 1985-Kobs, PS #14097; LCRC L.3765, Pg.515 - Fnd 1/2" Iron Bar in a Monument Box
 2.) 1985-Kobs, PS #14097; Survey L.3765, Pg.484 - Fnd 1/2" Iron in a Monument Box, used same wit as 1985 LCRC
 3.) 1989-Kobs, PS #14097; Survey L.4621, Pg.447 - Fnd 1/2" Iron Bar w/cap #14097 in a Monument Box, used same wit as 1985 LCRC

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 5-27-95

William E. Soderberg
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd 1/2" Iron Rod w/cap #14097 8" deep 10 feet South of the centerline of 28 Mile Road extending to the East & West, which has a gravel surface. Also 3 feet West of the centerline of Hayes Road extending to the South, which has a gravel surface. There is a fence-tree line extending to the North. Common corner to Sections 24 & 25, T4N, R12E, Washington Township (M-9) is located 32.70 feet to the North.

Witnesses from LCRC #1 were used to recover and verify the location of the found 1/2" Iron Rod w/cap #14097.

FIELD MEASUREMENTS BETWEEN

- A-9 to A-8 2735.83 Ft.
 A-9 to M-9 (Washington Twp.) 32.70 Ft. to the North, GLO = 96 links or 63.36 Ft.
 A-9 to A-10 2697.81 Ft.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-9 I set a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" on the township line 0.45 feet East of the found 1/2" Iron Rod w/cap #14097.
 N17°W 62.52' Set PK & Remon. Washer East face Power Pole
 S42°E 36.69' Chiseled cross in big rock
 S21°W 60.89' Set PK & Remon. Washer East face 29" Poplar
 S67°W 61.30' Set PK & Remon. Washer NW face 6" Poplar
 South 32.70' corner common to Sections 24 & 25, T4N, R12E, Washington Township (M-9)

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature]
 Surveyor's Michigan License No. 17623

Date June 2, 1995

