

SURVEY & REMONUMENTATION

C0214644 LIBER:06670 PAGE:222 10:16A 06/13/1995
 CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS

APR 29 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Macomb Located In: Ray Twp. Corner Code #
(County)

1. Public Land Survey	T	<u>4N</u>	R	<u>13E</u>	<u>A-11</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Huston K. Kennedy, in a field survey on April 28, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 1817-GLO Preston, D.S.; Set Post 6" Ironwood S38°W 6 Links; 12" Beech S60°E 24 Links
 1.) 1973-Avey, PS #15396; LCRC L.2426, Pg.343 - Fnd 1 1/4" Bar in a Monument Box
 2.) 1973-Avey, PS #15396; Survey L.2393, Pg.192 - Fnd 1 1/4" Bar in a Monument Box
 3.) Anderson, Eckstein & Westrick - Unrecorded Witnesses - Fnd 1 1/4" Bar in a Monument Box
 4.) 1987-Donnelly & Associates, Inc. - Unrecorded Survey - fnd Iron Rod

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 5-23-95.
William E. Soderberg
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1995 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd 1 1/4" Iron Bar in a Monument Box in the centerline of Hayes Road extending to the North, which has a gravel surface and 15 feet South of the centerline of 27 Mile Road extending to the East & West, which has a bituminous surface. There is a tree line extending to the South. The corner common to Sections 25 & 36, T4N, R12E, Washington Township, (M-11) is located 62.62 feet to the North.

Witnesses from LCRC #1 were used to recover and verify the location of the found 1 1/4" Iron Bar in a Monument Box.

FIELD MEASUREMENTS BETWEEN

- A-11 to A-10 2692.04 Ft.
- A-11 to A-12 2688.14 Ft.
- A-11 to M-11 (Washington Twp.) 62.62 Ft. to the South, GLO = 95 links or 62.70 Ft.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 A-11 I replaced the found 1 1/4 Iron Bar with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" in a existing Monument Box.
 N27°W 90.04' Set PK & Remon. Washer West face Power Pole
 N32°E 56.09' Set PK & Remon. Washer NW face Power Pole
 S10°E 106.78' Set PK & Remon. Washer West face Guide Pole
 S44°E 34.24' Set PK & Remon. Washer NE face Power Pole
 North 62.62' corner common to Sections 25 & 36, T4N, R12E, Washington Township (M-11)

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by *H K Kennedy*
 Surveyor's Michigan License No. 17623

Date June 1, 1995

