

APR 29 1996

COMMISSION

C0212008 LIBER:06663 PAGE:865 12:21P 06/06/1995  
CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Macomb  
(County)

Located In: Ray Twp.

Corner Code #

- 1. Public Land Survey T 4N R 13E A-12  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Huston K. Kennedy, in a field survey on April 28, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Preston, D.S.; Post not set
- 1.) 1973-Avey, PS #15396; LCRC L.2426, Pg.345 - Fnd 1" Pipe.
- 2.) 1973-Avey, PS #15396; Survey L.2393, Pg.192 - Fnd 1" Pipe.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 5-23-95  
William E. Soderberg  
WILLIAM E. SODERBERG, P.S., CHAIRMAN

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd 1" Iron Pipe 4" above ground with a tree-fence row extending to the East, and a tree-fence row extending to the North & South. The East 1/4 corner of Section 36, T4N, R12E, Washington Township, (M-12) is located 38.82 feet to the North.

Witnesses from LCRC #1 were used to recover and verify the location of the found 1" Iron Pipe.

FIELD MEASUREMENTS BETWEEN

- A-12 to A-11 2688.14 Ft.
- A-12 to A-13 2673.75 Ft.
- A-12 to M-12 (Washington Twp.) 38.82 Ft. to the North

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-12 I replaced the found 1" Iron Pipe with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623"  
Due North 14.02' Set PK & Remon. Washer West face 12" Ash  
N17°W 17.10' Set PK & Remon. Washer SW face 10" Ash  
N81°W 8.45' Set PK & Remon. Washer NE face 11" Hickory  
S46°W 28.11' Set PK & Remon. Washer NW face 13" Basswood  
North 38.82' East 1/4 corner of Section 36, T4N, R12E, Washington Township (M-12)

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by Huston K. Kennedy  
Surveyor's Michigan License No. 17623

Date May 30, 1995

