

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Macomb
 (County)

Located In: Ray Twp. Corner Code #

1091831
 LIBER 9268 PAGE 19
 12/27/1999 01:15:42 P.M.
 MACOMB COUNTY, MI
 CARMELLA SABAUGH, REG/DEEDS

1. Public Land Survey T-4-N R-13-E C-11
SURVEY &
REMONICATION
 2. Property Controlling S T R
 in Section S T R MAR 17 2000
 3. Miscellaneous S T R
 Property in Sec. S T R SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, John N. Redash, in a field survey on Jan. 14, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2			1
3												
4	7		8		9		10		11			12
5												
6	18		17		16		15		14			13
7												
8	19		20		21		22		23			24
9												
10	30		29		28		27		26			25
11												
12	31		32		33		34		35			36
13												

A. Description of original monument and accessories and/or subsequent restoration:

1817	Set post	G.L.O.	W. Preston	N/A	N/A
1974	1/2" pipe in mon. box	LCRC	H. Kobs	#14097	L2516, P84
1974	1/2" pipe in mon. box	Survey	H. Kobs	#14097	L2516, P78
1975	1/2" pipe in mon. box	Survey	H. Kobs	#14097	L2590, P334 and P423 L2548 P974
1976	1/2" pipe in mon. box	Survey	H. Kobs	#14097	L2653, P36
1979	1/2" pipe in mon. box	Survey	H. Kobs	#14097	L3186, P893
1981	1/2" pipe in mon. box	Survey	H. Kobs	#14097	L3331, P470
1984	1/2" pipe in mon. box	Survey	D. King	#30085	L3705, P111
1992	1/2" pipe in mon. box	Survey	D. King	#30085	L5831, P253
1994	Mon. box	Survey	G. James	#19835	L6434, P753
1998	1/2" pipe in mon. box	Survey	D. King	#30085	L8045, P16

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A monument box with remains of an old pipe in asphalt pavement at the intersection of 27 Mile Rd. and Romeo Plank Rd. currently occupies this corner. The following witness ties were used to re-establish this corner:
 3 ties from the LCRC recorded in L.2516 P.84.

Field measurements were observed between the following corners:

B-11 to C-11	C-11 to D-11	C-11 to C-12
2668.67 meas.	2694.38 meas.	2667.59 meas.
2640.00 Rec. G.L.O.(40 Chains)	2651.22 Rec. G.L.O.(40.17 Chains)	2640.00 Rec. G.L.O.(40 Chains)
2668.47 Rec. Survey L2590 P334	2694.21 Rec. Survey L2590 P423	2667.89 Rec. Survey L6434 P753
2668.67 Rec. Survey L2590 P334	2694.41 Rec. Survey L8045 P016	2667.49 Rec. Survey L8045 P007

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced remnants of an existing pipe with a 3/4" x 24" iron rod with a 2" dia. aluminum cap stamped "Macomb County Monument Act 345 #37281" in an existing mon. box.

Witnesses are as follows:

N. 45° E.	72.85'	S.W. corner of Methodist Church (Woodsided)
S. 45° E.	77.05'	N.W. corner of stone foundation to house #58974
S. 45° E.	37.40'	Set mag nail and Macomb County Remon Tag in utility pole
S. 45° W.	64.55'	Set mag nail and Macomb County Remon Tag in north face of 24" wall
N. 45° W.	60.90'	S.E. corner of building #59015 - (wood face)



The selected location is accepted by me and generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by John N. Redash

Date 11/22/99

Surveyor's Michigan License No. 37281

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1977

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 9/28/99

William E. Soderberg
 WILLIAM E. SODERBERG, P.S., CHAIRMAN