

APR 07 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Macomb
(County)

Located In: Ray Twp.

Corner Code #

- 1. Public Land Survey T-4-N R-13-E I-13
 T R
 T R
 T P
- 2. Property Controlling S T F
 in Section S T F
- 3. Miscellaneous S T R
 Property in Sec. S T R

C0623B21 LIBER:07784 PAGE:398 08:57A 12/22/1997
CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, John N. Redash, in a field survey on October 16, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

1817	Set post	G.L.O. Notes	W. Preston	N/AN/A	
1978	P.K. nail in pavement	Survey	G. James	#19835	L3010, P271
1991	P.K. nail in pavement	Survey	D. King	#30085	L5778, P394
1995	P.K. nail in pavement	L.C.R.C.	D. King	#30085	L6586, P211

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A found capped iron #19835 in an existing monument box in asphalt pavement currently occupies this corner. The following witness ties were used to recover and verify its position: 3 ties match current measurements from both survey witnesses and L.C.R.C. (L3010, P271, L5778, P394 and L6586, P211). Field observations were obtained between the following corners:

H-13 to I-13	I-13 to J-13	I-1 to I-13
2703.40 meas.	2678.76 meas.	100.72 meas.
2640.00 Rec. G.L.O.	2640.00 Rec. G.L.O.	100.58 Rec. Survey, L3010, P271
	2679.11 Rec. Survey	100.62 Rec. Survey L5778, P394

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the capped iron in an existing monument box with a 3/4" X 24" iron rod with a 2" aluminum disk stamped "Macomb County Monument MI Act 345 #37281". Witnesses are as follows:

- N. 53° E. 48.30' Set P.K. Nail and Macomb County Remon. washer N.W. face U-pole
- S. 15° E. 35.18' Found MDOT aluminum disk in concrete
- N. 70° W. 133.79' Set P.K. Nail and Macomb County Remon. washer S. face U-pole
- N. 30° W. 84.83' Set. P.K. nail and Macomb County Remon. washer N.E. face 6" Ash
- N. 05° W. 114.08' Set P.K. nail and Macomb County Remon. washer E. face U-pole

Due west 100.72' Macomb County Remon Cap #37281 in monument box (I-1, T-3-N., R-13-E.)

The selected location is accepted by me and generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by John N. Redash
Surveyor's Michigan License No. 37281

Date December 16, 1997



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1996

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 11-18-97
William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

701