

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

APR 07 1998

For corners in

Macomb (County) Located In: Ray Twp. Corner Code #
1. Public Land Survey T-4-N R-13-E L-13
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

SECTION

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 11-18-97

Signature of William E. Soderberg, P.S., Chairman

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 1-13. Cell 13-M contains a black dot.

I, John N. Redash, in a field survey on October 17, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Table with columns: Year, Description, G.L.O. Notes, Name, File #, Survey #. Rows include 1817 Set post, 1987 Found 1" pipe, 1992 3/4" pipe in mon. box, 1994 1" Pipe in mon. box, 1994 1" Pipe in mon. box.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A found 1/2" pipe in an existing monument box in asphalt pavement 0.5' ± north of centerline of 26 Mile Road currently occupies this corner. The following witness ties were used to recover and verify its position; 3 ties match current measurements from L.C.R.C. L4336, P172 and surveys L5633, P34, L6300, P929, L6245, P35. Corner L-13 is common with Corner L-1. Field observations were obtained between the following corners:

Table with columns: Corner pair, Measurement. Rows: K-13 to L-13 (2692.88 meas.), L-13 to M-13 (2696.63 meas.), 2692.92 Rec. Survey L6300, P929, 2696.83 Rec. Survey L5633, P34, 2640.00 Rec. G.L.O., 2640.00 Rec. G.L.O.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the found 1/2" pipe in the existing monument box with a 3/4" X 24" iron rod with a 2" aluminum cap. Witnessed and "Macomb County Monument MI Act 345 #37281". Witnesses are as follows:

Table with columns: Bearing, Distance, Description. Rows: N. 70° W. 101.20' P.K. Nail and Macomb County Remon. tag south face U-pole, N. 18° E. 28.14' P.K. Nail and Macomb County Remon. tag southeast face U-pole, N. 85° E. 140.03' P.K. Nail and Macomb County Remon. tag southeast face U-pole, S. 73° E. 156.65' P.K. Nail and Macomb County Remon. tag north face U-pole, S. 10° W. 31.90' P.K. Nail and Macomb County Remon. tag east face U-pole



The selected location is accepted by me and generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by John N. Redash

Date December 17, 1997

Surveyor's Michigan License No. 37281