

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

**SURVEY &
 REMONUMENTATION**

For corners in

MACOMB
 (County)

Located In: RAY TOWNSHIP Corner Code #

APR 07 1998

SECTION

- | | | | |
|------------------------------------|---------------|-----------------------------|-------------|
| 1. Public Land Survey | | <u>T 4 N. R 13 E.</u> | <u>M-11</u> |
| | | T <u> </u> R <u> </u> | <u> </u> |
| | | T <u> </u> R <u> </u> | <u> </u> |
| | | T <u> </u> R <u> </u> | <u> </u> |
| 2. Property Controlling in Section | S <u> </u> | T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> | T <u> </u> R <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Sec. | S <u> </u> | T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> | T <u> </u> R <u> </u> | <u> </u> |

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 11-7-97

William E. Soderberg
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
 5. Private Claims

I, ROBERT H. BIRKETT, in a field survey on JULY 22, 1997 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 10 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:
 1817, W. PRESTON D.S., SET CEDAR POST, G.L.O.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 FOUND 1/2" WATER PIPE 52.65' SOUTH OF A 1/2" IRON SOUTH OF A POINTED STONE, LOCATED SOUTH OF ABANDONED 27 MILE ROAD. 400' +/- EAST OF OMO ROAD.

| | |
|---|---|
| DISTANCES M-11 TO M-10 G.L.O. 40 CHAINS FIELD (GRID) 2733.32 FEET | DISTANCES M-11 TO M-12 G.L.O. 40 CHAINS FIELD (GRID) 2663.38 FEET |
|---|---|

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 REMOVED WATER PIPE AND REPLACED WITH A 36" LONG 1/2" R.R. ENCASED IN 4" OF CONC. WITH 2" DIAMETER ALUMINUM CAP STAMPED "MACOMB COUNTY MONUMENT MI ACT 345 M-11, 41094"

- AZ. 0° - 52.65' - MACOMB COUNTY REMON. CAP FOR A-11 LENOX TOWNSHIP
- AZ. 105° - 27.22' SET P.K. NAIL W/MACOMB COUNTY REMON. TAG IN N. FACE 4" HICKORY.
- AZ. 250° - 10.08' - SET P.K. NAIL W/MACOMB COUNTY REMON. TAG IN 4" ASH.
- AZ. 295° - 19.72' - SET P.K. NAIL W/MACOMB COUNTY REMON. TAG IN NORTHEAST FACE 4" HAWTHORN.



Signed by *Robert H. Birkett* Date 12/10/97
 Surveyor's Michigan License No. 41094

720