

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

**SURVEY &  
REMONUMENTATION**

For corners in

MACOMB  
(County)

**LENOX TOWNSHIP**  
Located In: Corner Code #

MAR 15 1999

SECTION

1. Public Land Survey		<u>T 4 N R 14 E</u>	<u>A-8</u>
		T <u>    </u> R <u>    </u>	<u>    </u>
		T <u>    </u> R <u>    </u>	<u>    </u>
		T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling in Section	S <u>    </u>	T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u>	T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	S <u>    </u>	T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u>	T <u>    </u> R <u>    </u>	<u>    </u>

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 10/27/98

*William E. Soderberg*  
WILLIAM E. SODERBERG, P.S., CHAIRMAN

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, ROBERT H. BIRKETT, in a field survey on June 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

A-8 THIS CORNER WAS NOT SET BY THE GENERAL LAND OFFICE.  
NO PREVIOUS RECORDINGS OR SURVEY INFORMATION WAS AVAILABLE FOR CORNER.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
A-8 SET 1/2" x 36" IRON, ENCASED IN 4" CONCRETE ON THE EXTENSION OF THE EAST AND WEST QUARTER LINE OF SECTION 19, LENOX TOWNSHIP (AS OCCUPIED AND SURVEYED), AND THE EAST LINE OF SECTION 24, RAY TOWNSHIP (AS MONUMENTED BY THIS PROGRAM).

REFERENCE SURVEY DATED 1991 BY R. STECKER, No. 30103.

**FIELD MEASUREMENTS**

A-8 TO A-7, GLO (1817) - NONE  
NO PREVIOUS RECORDED DISTANCE.  
RE-MONUMENTATION (1998) -2697.41'

M-12 TO M-13, GLO (1817) - 40 CHAINS (2640')  
NO PREVIOUS RECORDED DISTANCE.  
RE-MONUMENTATION (1998) - 2704.37'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
A-8 SET 1/2" x 36" IRON, ENCASED IN 4" CONCRETE WITH A 2" DIAMETER ALUMINUM CAP STAMPED "MACOMB COUNTY MONUMEN MI ACT 345, #41094, A-8".

- AZ. 0° - 5.70' - FOUND 1/2" IRON W/CAP No. 15405.
- AZ. 135° - 150.15' - SET MACOMB RE-MON TAG ABOVE FORM NAIL IN NORTH FACE UTILITY POLE.
- AZ. 180° - 31.05' - M-8, TOWN 4 NORTH, RANGE 13 EAST, RAY TOWNSHIP, MACOMB COUNTY.
- AZ. 180° - 67.23' - FOUND 1/2" IRON W/CAP No. 17097.
- AZ. 230° - 66.88' - SET MACOMB RE-MON TAG IN WEST FACE UTILITY POLE.

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C0865228 LIBER:08571 PAGE:776 09:29A 01/21/1999  
CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS



Signed by *Robert H. Birkett* Date 12-30-98  
Surveyor's Michigan License No. 41094