

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

**SURVEY &  
 REMONUMENTATION**

For corners in

MACOMB  
 (County)

Located In: LENOX TOWNSHIP Corner Code # \_\_\_\_\_

APR 07 1998

- |                                    |         |                     |            |
|------------------------------------|---------|---------------------|------------|
| 1. Public Land Survey              |         | <u>T 4 N R 14 E</u> | <u>A-9</u> |
|                                    |         | T _____ R _____     | _____      |
|                                    |         | T _____ R _____     | _____      |
|                                    |         | T _____ R _____     | _____      |
| 2. Property Controlling in Section | S _____ | T _____ R _____     | _____      |
|                                    | S _____ | T _____ R _____     | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ | T _____ R _____     | _____      |
|                                    | S _____ | T _____ R _____     | _____      |

SECTION

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 11/4/97

*William E. Soderberg*  
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, ROBERT H. BIRKETT, in a field survey on JULY 22, 1997 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817, W. PRESTON, CEDAR POST, 50 LINKS SOUTH OF M-9, RAY TOWNSHIP, T. 4 N., R. 13 E.
- 1972, G. AVENDT, No. 16034, FOUND 1" IRON PIN, SURVEY L. 2327, P. 131-135..
- 1972, G. AVENDT, No. 16034, FOUND 1" IRON PIN, L.C.R.C. L. 2327, P. 145.
- 1977, G. AVENDT, No. 16034, FOUND 1" IRON PIN, SURVEY L. 2870, P. 769.
- 1973, D. SCOTT, No. 12029, FOUND 1" SOLID IRON BAR, L.C.R.C. L.2429, P. 709.
- 1988, D. KING, No. 30085, FOUND 1" IRON BAR, SURVEY L. 4543, P. 130.
- 1991, H. KOBBS, No. 14097, FOUND 1" IRON BAR, SURVEY L. 5300, P. 231.
- 1994, D. KING, No. 30085, FOUND 1" IRON BAR, SURVEY L. 6595, P. 734.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" IRON BAR .5" DEEP IN A GRAVEL ROAD 2' SOUTH OF NORTH EDGE. NO FENCE OCCUPATION TO THE NORTH OR SOUTH. FENCE OCCUPIES THE SOUTH RIGHT OF WAY LINE OF 28 MILE ROAD TO THE SOUTH. PRIOR HISTORY COMMON WITH M-9, RAY TOWNSHIP, T. 4 N., R. 13 E.

MONUMENT MATCHES THE WITNESSES (SECTION "C") OF THE ABOVE DESCRIBED DOCUMENT (SECTION "A").

DISTANCES A-9 TO A-8  
 G.L.O. NOT RECORDED  
 FIELD (GRID) 2673.32 FEET

DISTANCES A-9 TO A-10  
 G.L.O. NOT RECORDED  
 FIELD (GRID) 2723.20 FEET

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REMOVED 1" IRON BAR AND REPLACED WITH A 3/4" X 24" IRON WITH A 2" DIAMETER ALUMINUM CAP STAMPED "MACOMB COUNTY MONUMENT MI ACT 345" M-9, A-9, 41094".

- AZ. 0° - 32.85' - FOUND 1/2" IRON W/CAP No. 14097.
- AZ. 170° - 46.04' - FOUND P.K. NAIL IN SOUTHWEST FACE 8" ELM.
- AZ. 180° - 33.95' - FOUND P.K. NAIL IN EAST FACE 12" OAK.
- AZ. 205° - 35.04' - FOUND P.K. NAIL IN WEST FACE 5" OAK.



Signed by Robert H. Birkett Date 12/10/97  
 Surveyor's Michigan License No. 41094

711