

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MACOMB
 (County)

LENOX TOWNSHIP
 Located In: Corner Code #

1091818
 LIBER 9268 PAGE 1
 12/27/1999 01:15:12 P.M.
 MACOMB COUNTY, MI
 CARMELLA SABAUGH, REG/DEEDS

1. Public Land Survey T 4 N R 14 E B-13
T R
T R SURVEY &
T R MONUMENTATION
 2. Property Controlling S T R
 in Section S T R
 3. Miscellaneous S T R
 Property in Sec. S T R
 MAR 17 2000
SECTION

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 10/5/99

William E. Soderberg
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, ROBERT H. BIRKETT, in a field survey on JULY 22, 1997 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
 B-13 LENOX.

- 1817, W. PRESTON, GLO, SET WOOD POST
- (a) 1934, MACOMD COUNTY ROAD COMMISSION, FOUND IRON PIPE, CORNER CARD.
- (b) 1972, H. KOBS #14097, UNDETERMINED MONUMENT, SURVEY L. 2291, P. 645 MCR.
- (c) 1972, H. KOBS #14097, UNDETERMINED MONUMENT, LCRC L. 2291, P. 654 MCR.
- (d) 1977, W. COULTER #14760, FOUND 3/4" PIPE, LCRC L. 2839, P. 832 MCR.
- (e) 1977, H. KOBS #14097, FOUND P.K. NAIL IN PAVEMENT, SURVEY L. 2882, P. 472 MCR.
- (f) 1988, D. KING #30085, FOUND P.K. NAIL IN PAVEMENT, SURVEY L. 4621, P. 480 MCR.
- (g) 1989, D. KING #30085, FOUND P.K. NAIL IN PAVEMENT, SURVEY L. 4866, P. 844 MCR.
- (h) 1989, D. KING #30085, FOUND P.K. NAIL IN PAVEMENT, SURVEY L. 4866, P. 854 MCR.
- (i) 1990, D. KING #30085, FOUND P.K. NAIL IN PAVEMENT, LCRC L. 4866, P. 808 MCR



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 B-13 LENOX. FOUND P.K. NAIL IN THE CENTER OF 26 MILE ROAD (ASPHALT) 2.36' WEST OF A MONUMENT BOX.
 NORTH - (b, c, e, f, g, h) 31.71' (d) 31.88', - P.K. IN TOP OF CORNER POST.
 NNE - (g, h, i) 26.58' - P.K. NAIL IN 4" ASH GROUP
 SW - (g, h, i) 76.31' - NAIL & WASHER IN D.E. POLE.

FIELD MEASUREMENTS (SEE BACK FOR SKETCH)			
B-13 TO A-13 LENOX	B-13 TO C-13LENOX	B-13 TO B-1 CHESTERFIELD	B-13 TO C-1 CHESTERFIELD
GLO 71.5 CHAINS. (4719.0')	GLO 40 CHAINS (2640')	GLO (NONE)	GLO (NONE)
RE-MON.(1999) - 4870.57'	RE-MON. (1999) - 2749.78'	RE-MON. (1999) - 2168.13'	RE-MON. (1999) - 521.33

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 B-13 LENOX. REMOVED EXISTING P.K. NAIL AND SET A 3/4" IRON WITH A 2" DIAMETER ALUMINUM CAP STAMPED "MACOMB COUNTY MONUMENT, M1 ACT 345, #41094, D-13" IN NEW MONUMENT BOX.

- AZ. 10° - 26.59' - SET REMON TAG ABOVE FOUND P.K. NAIL IN WEST FACE 6" ASH GROUP.
- AZ. 95° - 124.02' - SET REMON TAG ABOVE FOUND P.K. NAIL WWASHER IN NORTH FACE UTILITY POLE.
- AZ. 90° - 2.36' - FOUND 3/4" IRON IN MONUMENT BOX.
- AZ. 235° - 76.25' - SET REMON TAG ABOVE FOUND P.K. NAIL WWASHER IN NORTHWEST FACE UTILITY POLE.
- AZ. 335° - 31.78' - SET REMON TAG ABOVE FOUND P.K. NAIL WWASHER IN TOP ANCHOR POST.

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Robert H. Birkett Date NOVEMBER 23, 1999
 Surveyor's Michigan License No. 41094

gx ✓

944

MACOMB COUNTY
LENOX TOWNSHIP
TOWN 4 NORTH, RANGE 14 EAST

SURVEY &
REPRESENTATION
MAR 17 2000
SECTION

