

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MACOMB
 (County)

Located In: LENOX TOWNSHIP Corner Code #

**SURVEY &
 REMONUMENTATION**

APR 07 1998

SECTION

- | | | | |
|---------------------------------------|-------|-----------------------|-------------|
| 1. Public Land Survey | | <u>T 4 N. R 14 E.</u> | <u>C-13</u> |
| | | T ___ R ___ | _____ |
| | | T ___ R ___ | _____ |
| | | T ___ R ___ | _____ |
| 2. Property Controlling
in Section | S ___ | T ___ R ___ | _____ |
| | S ___ | T ___ R ___ | _____ |
| 3. Miscellaneous
Property In Sec. | S ___ | T ___ R ___ | _____ |
| | S ___ | T ___ R ___ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, ROBERT H. BIRKETT, in a field survey on JULY 22, 1997 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		13		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1817. W. PESTON D.S., SET CEDAR POST, G.L.O.
- 1978. H. KOBBS #14097, FOUND P.K. NAIL IN PAVEMENT, L.C.R.C. L. 3021, P. 211.
- 1995. D. KING #30085, SET P.K. NAIL IN PAVEMENT, L.C.R.C. L. 6656, P. 938, SURVEY L. 6668, P. 297.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- FOUND P.K. NAIL IN THE CENTERLINE OF ASPHALT 26 MILE ROAD AT THE INTERSECTION OF PLACE ROAD.
- | | |
|---------------------------|--|
| DISTANCES C-13 TO B-13 | DISTANCES C-13 TO C-1(CHESTERFIELD TWP. T. 3 N., R. 14 E.) |
| G.L.O. 40 CHAINS | G.L.O. NONE |
| FIELD (GRID) 2747.42 FEET | FIELD (GRID) 2228.86' |

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- REMOVED P.K. NAIL AND REPLACED WITH A 3/4" X 24" IRON WITH 2" DIAMETER ALUMINUM CAP IN MONUMENT BOX, STAMPED "MACOMB COUNTY MONUMENT MI ACT 345 C-13, 41094"
- AZ. 40° - 60.18' - FOUND P.K. NAIL IN WEST FACE SQUARE ANCHOR POST..
 - AZ. 60° - 56.51' - FOUND P.K. NAIL IN SOUTHEAST FACE UTILITY POLE.
 - AZ. 120° - 93.89' - FOUND P.K. NAIL IN SOUTHWEST FACE 12" ASH.
 - AZ. 170° - 34.14' - FOUND P.K. NAIL IN WEST FACE UTILITY POLE.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 11-4-97
William E. Soderberg
 WILLIAM E. SODERBERG, P.S., CHAIRMAN



Signed by Robert H. Birkett Date 12/10/97
 Surveyor's Michigan License No. 41094