

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MACOMB

(County)

LENOX TOWNSHIP

Located in:

Corner Code #

1091819
 LIBER 9268 PAGE 3
 12/27/1999 01:15:14 P.M.
 MACOMB COUNTY, MI
 CARMELLA SABAUGH, REG/DEEDS

1. Public Land Survey

T 4 N R 14 E

D-13

T _____ R _____

T _____ R _____

T _____ R _____

SURVEY &
 RESTORATION

2. Property Controlling
 in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
 Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

MAR 17 2000

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, ROBERT H. BIRKETT, in a field survey on JULY 10, 1999 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- D-13 LENOX. 1817 W. PRESTON, GLO, SET WOOD POST
- (a) 1934, MACOMB COUNTY ROAD COMMISSION, IRON PIN, CORNER FILE.
- (b) 1981, R. SMITH #16052, IRON IN MON. BOX, SURVEY L. 3383, P. 581 MCR.
- (c) 1993, W. SODERBERG #17635, 5/8" REBAR, L.C.R.C. L. 6325, P. 320 MRC.
- (d) 1994, D. KING #30085, 3/4" IRON IN MON BOX, L.C.R.C. L. 6586, P. 195 MCR.
- (e) 1997, D. KING #30085, 3/4" IRON IN MON BOX, SURVEY L. 8044, P. 901 MCR.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 10/5/99

William E. Soderberg
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- D-13 LENOX. FOUND 5/8" IRON IN A MONUMENT BOX AT INTERSECTION OF 26 MILE ROAD (ASPHALT) AND BATES ROAD NORTH (GRAVEL)
- NE - (c 61.45', d, e 61.52') - P.K. NAIL W/MCRC TAG IN EAST FACE U.P.
- SW - (c 48.75', d, e 48.67') - P.K. NAIL W/MCRC TAG IN SOUTHEAST FACE U.P.
- NW - (c 40.08', d, e 40.10') - P.K. NAIL W/MCRC TAG IN EAST FACE U.P.
- NNW - (c 102.67') - P.K. NAIL W/TAG #17635 IN EAST FACE U.P.

FIELD MEASUREMENTS

(SEE SKETCH ON BACK)

D-13 TO C-13 LENOX	D-13 TO E-13 LENOX	D-13 TO D-1 CHESTERFIELD	D-13 TO E-1 CHESTERFIELD
GLO (1817) - 40 CHAINS (2640')	GLO (1817) - 40 CHAINS (2640')	GLO ((NONE)	GLO ((NONE)
R. SMITH (1981) - 2728.85'	D. KING (1997) - 2725.72'	RE-MON (1999) - 2243.47'	RE-MON (1999) - 470.73'
RE-MON. (1999) - 2729.62'	RE-MON. (1999) - 2726.01'		

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 D-13 LENOX REMOVED 5/8" IRON AND SET A 3/4" IRON WITH A 2" DIAMETER ALUMINUM CAP STAMPED
 COUNTY MONUMENT, MI ACT 345, #41094, D-13" IN EXISTING MONUMENT BOX.

- AZ. 30° - 61.57' - FOUND P.K. NAIL WITH MCRC TAG IN EAST FACE TELEPHONE POLE.
- AZ. 105° - 161.40' - SET REMON TAG IN NORTH FACE UTILITY POLE.
- AZ. 235° - 48.66' - FOUND P.K. NAIL WITH MCRC TAG IN SOUTHEAST FACE UTILITY POLE.
- AZ. 335° - 40.15' - FOUND P.K. NAIL WITH MCRC TAG ABOVE A NAIL IN NORTHEAST FACE UTILITY POLE.
- AZ. 355° - 102.67' - FOUND P.K. NAIL W/#17635 TAG IN EAST FACE UTILITY POLE.

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.



Signed by Robert H. Birkett Date NOVEMBER 23, 1999
 Surveyor's Michigan License No. 41094

a45

MACOMB COUNTY
LENOX TOWNSHIP
TOWN 4 NORTH, RANGE 14 EAST

SURVEY &
RECONSTITUTION

MAR 17 2000

SECTION

