

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>MACOMB</u> (County)	LENOX TOWNSHIP Located In:	Corner Code #
1. Public Land Survey	T <u>4 N</u> R <u>14 E</u>	<u>E-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

SURVEY &
 RE-MONUMENTATION

MAR 17 2000

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, ROBERT H. BIRKETT, in a field survey on JULY 10, 1999 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- E-13 LENOX. 1817 W. PRESTON, GLO, SET WOOD POST
- (a) 1973, H. KOBS # 14097, 1/2" STEEL BOLT IN MONUMENT BOX, SURVEY, L. 2449, P. 81 M.C.R.
- (b) 1973, H. KOBS # 14097, 1/2" STEEL BOLT IN MONUMENT BOX, L.C.R.C., L. 2449, P. 92 M.C.R.
- (c) 1974, H. KOBS # 14097, 1/2" STEEL BOLT IN MONUMENT BOX, SURVEY, L. 2516, P. 76 M.C.R.
- (d) 1977, H. KOBS # 14097, 1/2" STEEL BOLT IN MONUMENT BOX, SURVEY, L. 2882, P. 450 M.C.R.
- (e) 1997, D. KING, # 30085, 1/2" IRON BAR IN MONUMENT BOX, SURVEY, L. 8044, P. 91 M.C.R.
- (f) 1997, W. SODERBERG, # 17635, FOUND IRON IN MONUMENT BOX, SURVEY, NOT RECORDED.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- E-13 LENOX. FOUND 1/2" BOLT IN MONUMENT BOX CENTER 26 MILE (ASPHALT) 0.8' DEEP @ INT. ROSSELL NORTH.
- N.W. (a, b, c, d, e 45.59') P.K. NAIL & M.C.R.C. CAP IN D.E. POLE.
- N.E. (a, b, c, d, e 82.70') P.K. NAIL & WASHER IN 24" POPULAR.
- S.W. (a, b, c, d, e 43.60') P.K. NAIL & WASHER IN D.E. POLE.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 10/15/99

William E. Soderberg
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

FIELD MEASUREMENTS

(SEE SKETCH ON BACK)

E-13 TO D-13 LENOX	E-13 TO F-13 LENOX	E-13 TO E-1 CHESTERFIELD	E-13 TO F-1 CHESTERFIELD
G.L.O. - 40 CHAINS (2640')	G.L.O. - 40 CHAINS (2640')	GLO (NONE)	GLO (NONE)
D. KING (1997) - 2725.72'	NO RECORDED DISTANCE	RE-MON (1999) - 2255.20'	RE-MON (1999) - 421.19'
RE-MON. (1999) - 2726.01'	RE-MON. (1999) - 2735.60'		

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-13 LENOX REMOVED 1/2" BOLT AND SET A 3/4" IRON WITH A 2" DIAMETER ALUMINUM CAP STAMPED "MACOMB COUNTY MONUMENT, MI ACT 345, #41094, E-13" IN EXISTING MONUMENT BOX.

- AZ 30° 82.29' - SET REMON. TAG ABOVE FOUND P.K. WITH WASHER WEST FACE 26" POPLAR.
- AZ 125° 56.76' - SET REMON TAG IN NORTHEAST FACE 8" ELM
- AZ 250° 44.85' - SET REMON TAG ABOVE FOUND P.K. WITH WASHER SOUTHEAST FACE TELEPHONE POLE.
- AZ 325° 45.62' - SET REMON TAG ABOVE FOUND P.K. NAIL IN EAST FACE TELEPHONE POLE.

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

9x2
 Signed by Robert H. Birkett Date NOVEMBER 23, 1999
 Surveyor's Michigan License No. 41094

946

MACOMB COUNTY
LENOX TOWNSHIP
TOWN 4 NORTH, RANGE 14 EAST
E-13

SURVEY &
RECORDS DEPARTMENT

MAR 17 2000

SECTION

