

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MACOMB
 (County)

LENOX TOWNSHIP
 Located In: Corner Code #

1. Public Land Survey T 4 N R 14 E G-13
 T ___ R ___
 T ___ R ___
 T ___ R ___
 T ___ R ___
 2. Property Controlling S ___ T ___ R ___
 in Section S ___ T ___ R ___
 3. Miscellaneous S ___ T ___ R ___
 Property in Sec. S ___ T ___ R ___

SURVEY &
 RE-MONUMENTATION
 MAR 17 2000
 SECTION

1091822
 LIBER 9268 PAGE 9
 12/27/1999 01:15:14 P.M.
 MACOMB COUNTY, MI
 CARMELLA SABAUGH, REG/DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, ROBERT H. BIRKETT, in a field survey on JULY 10, 1999 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 G-13 LENOX . 1817 W. PRESTON, GLO, SET WOOD POST
 (a) 1961, MSHD, WITNESS RECORD RAILROAD SPIKE IN 26 MILE ROAD.
 (b) 1992, M.C.R.C. WITNESS RECORD MONUMENTATION TYPE NOT INDICATED.
 (c) 1982, W. SODERBERG # 17635, 1/2" RE-ROD IN MONUMENT BOX, L.C.R.C., L. 3403, P. 775 M.C.R.
 (d) 1982, H. KOBBS # 14097, FOUND 1/2" IRON BAR IN PAVEMENT, L.C.R.C., L. 3465, P. 173 M.C.R.
 (e) 1988, G. WARD # 22445, FOUND 1/2" BAR IN MONUMENT BOX, L.C.R.C., L. 4546, P. 342 M.C.R.
 (f) 1988, STEPHENS # 29252, FOUND BAR 1/2" IN MONUMENT BOX, SURVEY, L. 5969, P. 139 M.C.R.
 (g) 1993, D. KING # 30085, 1/2" IRON IN MONUMENT BOX, L. 5969, P. 139 M.C.R.
 (h) 1994, D. KING # 30085, 1/2" IRON IN MONUMENT BOX, L.C.R.C., L. 6586, P. 196 M.C.R.
 (i) 1996, D. KING # 30085, 1/2" IRON IN MONUMENT BOX, SURVEY, L. 7430, P. 841 M.C.R.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 G-13 LENOX FOUND 1/2" IRON IN MONUMENT BOX .5" DEEP 1' SOUTH CENTER LINE 26 MILE ROAD (ASPHALT).
 N. (e 31.95') P.K. NAIL EAST FACE UTILITY POLE
 S.W. (e 156.34') SET P.K. DISC. NORTH FACE TRIPLE STEM ASH.
 N.W. (e 227.66') P.K. NAIL SOUTH FACE UTILITY POLE.
 N.W. (f 31.88') P.K. IN EAST FACE DETROIT EDISON POLE.
 N.W. (g, i 58.26') CHISELED X ON SOUTH RIM OF WATER GATE.

FIELD MEASUREMENTS
 G-13 TO F-13 LENOX G-13 TO G-1 CHESTERFIELD
 G.L.O. (1817) - 40 CHAINS (2640') GLO (NONE)
 D. KING (1993 & 1996) - 2724.55' RE-MONUMENTATION (199) - 2279.37'
 RE-MONUMENTATION (1999) - ~~2741.41'~~
 2724.41'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 G-13 LENOX. REMOVED 1/2" IRON AND SET A 3/4" IRON WITH A 2" DIAMETER ALUMINUM CAP STAMPED "MACOMB COUNTY MONUMENT, MI ACT 345, #41094, G-13" IN EXISTING MONUMENT BOX .


AZ 355° 32.01' - SET REMON TAG ABOVE FOUND P.K. NAIL EAST FACE UTILITY POLE.
 AZ 75° 217.89' - SET REMON TAG ABOVE FOUND P.K. NAIL WEST FACE UTILITY POLE.
 AZ 255° 105.50' - FOUND P.K. NAIL SOUTH END 12" CMP.
 AZ 275° 227.68' - SET REMON TAG ABOVE FOUND P.K. SOUTH FACE UTILITY POLE.
 AZ 315° 58.32' FD. CH. "+" SOUTHEAST RIM WATER GATE.

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Robert H. Birkett Date NOVEMBER 23, 1999
 Surveyor's Michigan License No. 41094

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5			4		3		2		1	
3													
4	7		8			9		10		11		12	
5													
6	18		17			16		15		14		13	
7													
8	19		20			21		22		23		24	
9													
10	30		29			28		27		26		25	
11													
12	31		32			33		34		35		36	
13													


ACCEPTED BY THE MACOMB COUNTY SURVEYORS' GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 10/15/99
 WILLIAM E. SODERBERG, P.S., CHAIRMAN



94 ✓

948

MACOMB COUNTY
LENOX TOWNSHIP
TOWN 4 NORTH, RANGE 14 EAST
G-13



SURVEY &
RECORDS SECTION

MAR 17 2000

SECTION

