

**SURVEY &  
REMONUMENTATION**

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

C152273

94 DEC 14 AM 10:55

CLERK OF COURTS  
REGISTER OF DEEDS  
MACOMB COUNTY, MI

corners in

<b>MACOMB</b> (County)	Located In: <b>LENOX TWP.</b>	Corner Code # <b>M-1</b>
Public Land Survey	T <u>4N</u> R <u>14E</u>	<u>M-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling in Section	S _____ T _____ R _____	_____
Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

LIBER 6527 PAGE 850

Register of Deeds Stamp & File Number

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
6												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

STEVEN E. DUNN, in a field survey on APRIL 4 19 94,  
hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points  
mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore  
required in the current manual of survey instructions of the United States Department of  
Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the  
corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the  
Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,  
established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be  
recorded on this certificate.**

Description of original monument and accessories and/or subsequent restoration:

**GLO POST - NO EVIDENCE OF ORIGINAL CORNER FOUND  
GLO ORIGINAL SURVEY PERFORMED BY PRESTON - 1817**

<u>L.C.R.C.</u>	<u>NAME AND NUMBER</u>	<u>DESCRIPTION</u>	<u>DATE</u>
L. 0001 P. 791 (ST. CLAIR COUNTY RECORDS)	HERBERT J. KOBS, #14097	FOUND 1/2" PIPE	MARCH 29, 1973
L. 3204 P. 459	ROBERT L. SMITH, #16052	FOUND 1/2" IRON	JANUARY 25, 1980

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

**M-1 TOWNSHIP CORNER FOUND 1/2" IRON ROD IN ASPHALT PAVEMENT. COMMON TO M-13 RICHMOND TWP.,  
A-1 CASCO TWP., AND A-13 COLUMBUS TWP.,  
VERIFIED LOCATION WITH FOUND WITNESSES OF ABOVE L.C.R.C.'s**

**FOUND WITNESS TIES**

L.C.R.C. L. 3204 P. 459	N.45°W. 91.98'	NAIL IN SOUTH FACE OF TELEPHONE POLE
	N.30°E. 34.83'	NAIL IN SOUTHEAST FACE OF TELEPHONE POLE
	S.45°W. 34.48'	NAIL IN NORTHEAST FACE OF POWER POLE
L.C.R.C. L. 0001 P. 791 (ST. CLAIR COUNTY RECORDS)	N.W. 47.68'	FORM NAIL AND WASHER IN 18" WILD CHERRY
	N.W. 91.98'	FORM NAIL AND WASHER IN BELL TELEPHONE POLE
	S.W. 34.45'	FORM NAIL AND WASHER IN DETROIT EDISON POLE



Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**M-1 T.4N., R.14E. I REPLACED 1/2" IRON ROD WITH 3/4" x 24" IRON ROD WITH 2" DIAMETER ALUMINUM CAP  
STAMPED "MACOMB COUNTY MONUMENT MI. ACT 345 #28408" IN A NEW MONUMENT BOX.**

**WITNESSES**

N.30°E. 34.83'	FOUND PK. NAIL IN SOUTHEAST FACE OF TELEPHONE POLE.
S.10°E. 58.23'	SET PK. NAIL WITH M.C.R. TAG IN EAST SIDE OF 6" OAK.
S.45°W. 34.45'	FOUND FORM NAIL IN NORTHEAST FACE OF UTILITY POLE.
N.45°W. 91.98'	FOUND FORM NAIL IN SOUTH FACE OF TELEPHONE POLE.

**ACCEPTED BY THE MACOMB COUNTY SURVEY PEER  
GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN  
PUBLIC ACT 345 OF 1980 AT A MEETING HELD  
ON 10-18-94**  
*William E. Soderberg*  
**WILLIAM E. SODERBERG, P.S., CHAIRMAN**

**THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST  
AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.**

signed by Steven E. Dunn Date Nov. 9, 1994  
Surveyor's Michigan License No. 28408