

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MACOMB  
(County)

**LENOX TOWNSHIP**  
Located In: Corner Code #

- |                                    |       |                     |            |
|------------------------------------|-------|---------------------|------------|
| 1. Public Land Survey              |       | <u>T 4 N R 14 E</u> | <u>M-3</u> |
|                                    |       | T ___ R ___         | _____      |
|                                    |       | T ___ R ___         | _____      |
|                                    |       | T ___ R ___         | _____      |
| 2. Property Controlling in Section | S ___ | T ___ R ___         | _____      |
|                                    | S ___ | T ___ R ___         | _____      |
| 3. Miscellaneous Property in Sec.  | S ___ | T ___ R ___         | _____      |
|                                    | S ___ | T ___ R ___         | _____      |

SURVEY &  
REMONUMENTATION

MAR 15 1999

SECTION

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, ROBERT H. BIRKETT, in a field survey on JUNE 8, 1998 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
1817, W. PRESTON, GLO, SET POST.

- 1) W.S. McALPINE #1015, SET CONCRETE MONUMENT, "SUP. PLAT No. 1", LENOX TOWNSHIP, L. 16 (PLATS), P. 44.  
2) 1983, H. KOBS #14097, SET P.K. NAIL. LCRC L. 3579, P. 147, MCR.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-3 FOUND P.K. NAIL UNDER .2' ASPHALT ON THE CENTERLINE OF COUNTY LINE ROAD AND 20' +/- SOUTH OF THE CENTERLINE OF 31 MILE ROAD.

69.27' (2) - NE - CENTER TOP OF CONCRETE MONUMENT. (FND. 69.09' TO A CORNER)  
20.58' (1) - NORTH - 5/8" IRON IN MON. BOX. (FND. 20.58') (GLO DISTANCE 0.32 LINKS)

ACCEPTED BY THE MACOMB COUNTY SURVEY PEOP  
GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN  
PUBLIC ACT 345 OF 1990 AT A MEETING HELD  
ON 9/29/98

*William E. Soderberg*  
WILLIAM E. SODERBERG, P.S., CHAIRMAN

FIELD DISTANCES

M-3 TO M-2, GLO (1817) - 40 CHAINS (2640')  
McALPINE (1936) - 2701.06'  
RE-MONUMENTATION (1998) - 2700.26'

M-3 TO M-4, GLO (1817) - 40 CHAINS (2640')  
NO PREVIOUS RECORDED DISTANCES  
RE-MONUMENTATION (1998) - 2681.56'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-3 REPLACED P.K. NAIL WITH A 3/4" X 24" RE-BAR IN NEW MONUMENT BOX AND A 2" DIAMETER ALUMINUM CAP STAMPED "MACOMB COUNTY MONUMENT, MI ACT 345, #41094, M-3".

- AZ. 0° - 20.58' - FOUND 1/2" IRON IN MONUMENT BOX, A-3 CASCO TOWNSHIP, ST. CLAIR COUNTY.  
AZ. 35° - 39.09' - NORTHWEST CORNER TRIANGULAR MONUMENT, FEDERAL AID PROJECT.  
AZ. 240° - 36.41' - SET MACOMB RE-MON TAG ABOVE P.K. NAIL IN SOUTHEAST FACE UTILITY POLE.  
AZ. 330° - 65.25' - SET MACOMB RE-MON TAG IN NORTHEAST FACE UTILITY POLE.

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C0865229 LIBER:08571 PAGE:777 09:29A 01/21/1999  
CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS

Signed by *Robert H. Birkett* Date 11-24-98  
Surveyor's Michigan License No. 41094

