

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

LENOX TOWNSHIP
 Located In: Corner Code #

MACOMB
 (County)

- | | | | |
|------------------------------------|-------|---------------------|------------|
| 1. Public Land Survey | | <u>T 4 N R 14 E</u> | <u>M-5</u> |
| | | T ___ R ___ | _____ |
| | | T ___ R ___ | _____ |
| | | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ | T ___ R ___ | _____ |
| | S ___ | T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ | T ___ R ___ | _____ |
| | S ___ | T ___ R ___ | _____ |

SURVEY &
 REMONUMENTATION

MAR 15 1999

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, ROBERT H. BIRKETT, in a field survey on JULY 18, 1998 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4		3			2	1
3													
4	7			8			9		10			11	12
5													
6	18			17			16		15			14	13
7													
8	19			20			21		22			23	24
9													
10	30			29			28		27			26	25
11													
12	31			32			33		34			35	36
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
SEE BACK
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 FOUND 1/2" IRON IN MONUMENT BOX INTERSECTION OF 30 MILE ROAD (GRAVEL) & COUNTY LINE ROAD (ASPHALT).

DISTANCE BETWEEN M-5 LENOX TWP., MACOMB CNTY. & A-5 CASCO TWP., ST CLAIR CNTY. (FND. 12.44') GLO .60 LINKS
 1, 2, 5, 6, 7) 12.40' 8) 12.43' 11) 12.50'
 5) 84.67' - SE TO NAIL IN E. FACE D.E.P. (FND. 84.64')
 8, 10) FND. SPIKE IN M.B.T. POLE AZ. 313° 39.50'.)FND. 39.19')
 9) N 45° E 55.80' P.K. S.E. SIDE P.P. (FND. 55.48')
 9) S 30° E 84.64' NAIL E. SIDE P.P. (FND. 84.64')
 10) NE 55.50' TO PK & SCCRC TAG (SE) DEP. (FND. 55.48')
 10) SE 62.75' TO NW FACE 3" DIA. COR. CHN. LINK FENCE POST. (FND. 62.75')

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 9/29/98
William E. Soderberg
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

FIELD MEASUREMENTS (SEE BACK)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 REPLACED 1" PIPE IN EXISTING MONUMENT BOX WITH A 3/4" X 24" RE-BAR WITH A 2" DIAMETER ALUMINUM CAP STAMPED "MACO COUNTY MONUMENT, MI ACT 345, #41094".

- AZ. 40° - 55.48' - P.K. NAIL IN SOUTHEAST FACE UTILITY POLE WITH A LIGHT.
- AZ. 90° - 70.90' - TIP OF NOTCH IN EAST END 12" CMP DRIVE CULVERT.
- AZ. 125° - 62.75' - 2" METAL POST @ NORTHWEST CORNER CHAIN LINK FENCE.
- AZ. 190° - 84.30' - P.K. NAIL WITH S.C.C.R.C./ TAG ABOVE A P.K. NAIL IN WEST FACE UTILITY POLE.
- AZ. 240° - 81.42' - P.K. NAIL WITH S.C.C.R.C. TAG IN SOUTH FACE 9" PINE.
- AZ. 300° - 35.20' - CENTER OF STORM MANHOLE.
- AZ. 300° - 39.19' - P.K. NAIL WITH S.C.C.R.C. TAG IN NORTHEAST FACE G.T.E. POST.
- AZ. 335° - 60.75' - P.K. NAIL WITH S.C.C.R.C. TAG IN NORTHEAST FACE G.T.E. POLE.
- AZ. 0° - 12.44' - 1/2" IRON IN MONUMENT BOX, A-5, CASCO TOWNSHIP, ST CLAIR COUNTY, T. 5 N., R. 15 E.



THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Robert H. Birkett Date 11-24-98
 Surveyor's Michigan License No. 41094

92
 817

SURVEY &
REMONUMENTATION

MAR 15 1999

SECTION

A. Description of original monument and accessories and/or subsequent restoration

FROM FRONT

1817 W. PRESTON, GLO, SET POST

- 1) UNKNOWN DATE, J. LANSKY #18659, P.K. NAIL, STATEMENT L 1 (SURVEYS), P. 868, S.C.C.R.
- 2) 1972, G. JAMES #19835, P.K. NAIL, L 1 (CORNERS), P. 574, S.C.C.R.
- 3) 1972, H. KOBBS #14097, 1/2" IRON BAR, SURVEY L 2377, P. 893, M.C.R.
- 4) 1973, H. KOBBS #14097, 1/2" IRON BAR IN CENTER JOINT OF PAVEMENT, L.C.R.C. L 2377, P. 905, M.C.R.
- 5) 1977, ST. CLAIR CO. ROAD COM., 1/2" STEEL PIN, FIELD NOTES.
- 6) 1979, R. KREGER #24601, P.K. NAIL, L 7 (SURVEYS), P. 71, S.C.C.R.
- 7) 1980, R. KREGER #24601, P.K. NAIL IN CENTERLINE, L 7 (SURVEYS), P. 403.
- 8) 1983, J. NELSON #21273, 1/2" IRON IN MONUMENT BOX, L.C.R.C. L 3547, P. 91, M.C.R.
- 9) 1987, R. BROWN #24588, 1/2" IRON IN MONUMENT BOX, SURVEY UNRECORDED.
- 10) 1995, ST. CLAIR COUNTY ROAD COM., 1/2" IRON IN MONUMENT BOX, FIELD NOTES.
- 11) 1996, M. ROSSOW #24615, MONUMENT BOX CENTERLINE, L 8 (CORNERS), P. 262, S.C.C.R.

FIELD MEASUREMENTS (FROM FRONT)

M-5 TO M-4, GLO (1817) - 40 CHAINS (2640)
KOBBS (1972) - 2694.62'
BRUEN (1985) - 2694.26'
S.C.C.R.C. (1995) - 2694.55'
LANSKY (UNKNOWN) - 2694.67'
RE-MONUMENTATION (1998) - 2694.38'

M-5 TO M-6, GLO (1817) - 40 CHAINS (2640)
LANSKY (UNKNOWN) - 2688.01'
S.C.C.R.C. (1995) - 2688.16'
RE-MONUMENTATION (1998) - 2688.17'

M-5 TO A-5 C+9 L0 GLO 39.6
Men 12.44